

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

JUN 04 2007

Form CP-1
September 2003

This Form must be Typed
Form must be Signed
All blanks must be Filled
CONSERVATION DIVISION
WICHITA, KS

API # 15-185-10457-00-02 ~~100-26303~~ (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 3/01/48

Well Operator: Dar Energy (Owner / Company Name) KCC License #: 33582 (Operator's)

Address: 300 SW 93rd St. City: Oklahoma City

State: Oklahoma Zip Code: 73139 Contact Phone: (405) 793 - 8701

Lease: McNaughten Well #: 1-B OWWO Sec. 27 Twp. 24 S. R. 13 East West

NW - NW - NW Spot Location / QQQQ County: Stafford

4965 330 Feet (in exact footage) From North South (from nearest outside section corner) Line of Section (Not Lease Line)

4984 330 Feet (in exact footage) From East West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 12 1/2 Set at: 412 Cemented with: 400 Sacks

Production Casing Size: 7 Set at: 4077 Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3718'-3727' 3732'-3737'

Elevation: 1932' (G.L. / K.B.) T.D.: 4091' PBDT: NA Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): as per KCC regulations

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? not available

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dar Energy

Phone: (405) 793 - 8701

Address: 300 SW 93rd St. City / State: Oklahoma City, OK

Plugging Contractor: Quality Well Service (Company Name) KCC License #: 31925 (Contractor's)

Address: 401 W. Main Lyons, KS Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5/30/2007 Authorized Operator / Agent: David W Brady (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

MURE IN DRLG & OSAGE O & G #1 McNAGHTEN 27-24-13W NE NE NE
 Contr. MURE IN DRLG STAFFORD County
 E. 1930 RB Comm. Comp. 9-6-57 IP 75 BOPD

Tops	Depth	Datum
HEEB	3389	-1159
TOR	3408	-1178
BR LM	3527	-1597
LANS	3555	-1625
VLO	3933	-2003
SIMP	4046	-2116
ARB	4098	-2168
TD	4134	-2204

Casing
 8" 263
 5" 4135
 DST 3598-3641/1 1/2 HR, G/I HR 35", 85' O & GCM, 120' MDY GSY O, 200' GSY O, 40' O & GCM, 75' W, BHP 1285#
 DST 3633-41/1 1/2 HR, 2500' G, 30' VHO & GCM, 140' MDY O, 100' W, BHP 1185#
 DST 3718-30/1 1/2 HR, G/I HR, 70' MDY GSY O, 220' FL, BHP 950#
 DST 3734-45/45", 18' MUD, BHP 960#
 DST 3794-3825/1 HR, 35' SL OCM, BHP 290#
 DST 3864-91/45", 17' M, SPKS O, NO BHP
 DST 4099-4104/1 1/2 HR, 3025' SW, BHP 1350#
 DST 4117-25/1 HR, 3050' SUL WTR, BHP 1385#
 PERF 3727-31: ACID 1000: PERF 3767-71: ACID 5000
 ST JOHN POOL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

ATLANTIC REFINING CO 27-24 -13W NW NW NW
 #1-B MCNAUGHTEN OWWO

site: 3-1/2 S OF ST JOHN KS city: STAFFORD API 15-IOG-26303
 contr: UNKNOWN field: ST JOHN
 geol:
 fr date 09/01/47 spd date 03/01/48 drig comp 03/01/48 card issued 09/01/47 last revised 05/31/93

ELV: 1932 GL LOG

tops.....	depth/datum
ANH.....	758 +1174
TOP.....	3074 -1142
LANS.....	3568 -1636
CONG.....	3905 -1973
VIOLA.....	3920 -1988
SIMP.....	4045 -2113
ARB.....	4075 -2143
TD OLD.....	4091 -2159

IP status:
 OIL, P 180 BO & 9.5 BWPD, LKC 3718-3737 OA,
 NOTE: INFO REL: 5/31/93 - ADDED MISC INFO
 OLD INFO: OPERATOR WAS ATLANTIC REFINING CO, 1 MCNAUGHTEN B, SPD 11/11/37, 12/28/37 12-1/2" 412 / 400 SX, 7" 4077 / 200 SX, OIL, P 1,449 BOPD, NW, ARB 4077-4091, (CARD ISSUED 09/01/47)
 CONTR: PARKER DRILLING
 IRON PYRITE AT 2522-2524
 POROUS LM ZNS: 3654-3661 (NS), 3697-3698 (SLI SO, SFT), 3728-3734 (GD SATR), 3740-3745 (GD SATR)
 DRLR SD ZNS: 30-115, 115-240 (W/GRVL), 240-360 (W/RED BED), 1906-1915, 2022-2100 (BRKN), 2115-2140 (SDY LM, GRV), 2140-2148 (WHT), 2148-2168 (SDY LM, GRV)

ATLANTIC REFINING CO

27-24 -13W
NW NW NW

#1-B MCNAUGHTEN OWWO

SALT ZNS: 1260-1489 (W/SH), 1545-1604, 1604-1635 (W/SH)

CORE (1) 3698-3702 (LKC), CUT 4', REC 3.5', REC 3.5' LM (SLI SO & SATR), 0.5' LOST

CORE (2) 3745-3752 (LKC), CUT 7', REC 6', REC 6.0' LM (GD SATR, SO), 1.0' LOST

CORE (3) 4080-4084 (ARB), CUT 4', FULL REC, REC 4.0' SILICEOUS LM (PRTLY PORO & SATR,
SME SH INTRSPERSED)

NO TSTS

MICT - CO, (ARB OH), AC 2000 GAL, FU 3800' OIL, NAT, POP, P 1449 BO, NW/24 HRS

NEW INFO: FR 09/01/47 , REWORKED 03/01/48 DC 03/01/48 MICT - CO, PB (DEPTH NA), PF
(LKC) 8/3718-3727, AC 1000 GAL, SO, PF (LKC) 36/3732-3737, SWB 10 BOPH/2 HRS, AC 5000
GAL, FU 300' BL (6% W)/12 HRS, POP, P 180 BO & 5% W



CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

DAR ENERGY LLC
300 SW 93RD ST.
OKLAHOMA CITY, OK 73139

June 07, 2007

Re: MCNAUGHTEN B #1
API 15-185-10457-00-02
27-24S-13W, 330 FNL 330 FWL
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well. **This notice is void after 180 days from its date. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely

Steve Bond
Production Department Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888