

Operator Name: C & E Oil Lease Name: Oliver Well #: Rogers H4
 Sec. 10 East West County: Chautauqua

ORIGINAL
 INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)
 Samples Sent to Geological Survey Yes No
 Cores Taken Yes No
 Electric Log Run Yes No
 (Submit Copy)
 List All E. Logs Run: Radio Activity cement bond

Name	Top	Datum
Base Kansas City	1444	-327
Altamont	1537	-420
Pawnee	1639	-522
Fort Scott	1691	-574
Cherokee	1736	-619
Mississippi	2015	-898
RTD	2089	-972

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
surface	12	8 5/8	20#	43	Portland	40	CCCL 1 sack
long string	7 7/8	5"	15.50	2079	Portland	340	Thick set

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type		Acid, Fracture, Shot, Cement Squeeze Record	
	Specify Footage of Each Interval Perforated		(Amount and Kind of Material Used)	
2	2010-2014	3 1/8 slick tag gen	1000 G 15% N&E	2010-2014
			1000 PSI shut end on vac	

TUBING RECORD				
Size	Set At	Packer At	Liner Run	
2 3/8	2026	none	<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No

Date of First, Resumerd Production, SWD or Enhr.	Producing Method			
4	<input type="checkbox"/> Flowing	<input checked="" type="checkbox"/> Pumping	<input type="checkbox"/> Gas Lift	<input type="checkbox"/> Other (Explain)

Estimated Production Per 24 Hours	Oil Bbbls.	Gas Mcf	Water Bbbls.	Gas-Oil Ratio	Gravity
	5	no test	60		34

Disposition of Gas Vented Sold Used on Lease (If vented, Submit ACO-1B.)
 METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled
 Production Interval Other (Specify) _____

ORIGINAL

BLUE STAR ACID SERVICE, INC.

PO Box 103
Eureka, Kansas 67045Cementing Ticket
and Invoice Number

No 5399

Date 4-5-04	Customer Order No.	Sect. 2	Twp. 32S	Range 10E	Truck Called Out	On Location 5:15 pm	Job Began 5:40 pm	Job Completed 6:00 pm
Owner C & E OIL		Contractor C & G DRILLING			Charge To C & E OIL			
Mailing Address RR1 Box 1 B2		City Moline			State KS			
Well No. & Form ROGERS # 4		Place			County CHAUTAUGUA 124		State KS	
Depth of Well 53'	Depth of Job 51'	Casing (New) Size 8 5/8 (Used) Weight 24 #	Size of Hole Amt. and Kind of Cement 1 1/4 40 SKS		Cement Left in casing by		Request Necessity 10' feet	
Kind of Job SURFACE					Drillpipe		Rotary Cable	
					Tubing		Truck No. #12	

Price Reference No.	# 1
Price of Job	425.00
Second Stage	
Mileage	307 67.50
Other Charges	
Total Charges	492.50

Remarks SAFETY Meeting: Rig up to 8 5/8 CASING. BREAK
Circulation with 10 BBL fresh water. Mixed 40
SKS Regular Cement with 3% CaCl₂. Displace
with 2 BBL fresh water. Shut casing in.
Good Cement Returns to SURFACE. Job Complete

Cementor KEVIN MCCOY
 Helper JUSTIN District Eureka State KS

The above job was done under supervision of the owner, operator, or his agent whose signature appears below.

Thank you

Called By Tim Gulick C & G PRI
Agent of contractor or operator

Sales Ticket for Materials Only

Quantity Sacks	BRAND AND TYPE	PRICE	TOTAL
40 SKS	Regular Class "A" Cement	7.75	310.00
112 #	CaCl ₂ 3%	.35	39.20
RECEIVED			
JUN 01 2004			
KCC WICHITA			
Plugs	40 SKS Handling & Dumping	.50	20.00
	1.88 Tws Mileage 30	.80	60.00 MLC
	Sub Total		921.70
	Discount		
Delivered by Truck No. #29	Delivered from EUREKA	Sales Tax 6.3%	58.07
Signature of operator <u>Kevin McCoy</u>		Total	979.77

ORIGINAL

BLUE STAR ACID SERVICE, INC.

PO Box 103
Eureka, Kansas 67045

Cementing Ticket
and Invoice Number

N^o 5419

Date 4-8-04	Customer Order No.	Sect.	Twp.	Range	Truck Called Out 3.00 AM	On Location 9.20 AM	Job Began 10.30 AM	Job Completed 11.30 AM
Owner C + E oil			Contractor C + G Drig			Charge To C + E oil		
Mailing Address RRI Box 1 B 2			City Moline			State Ks		
Well No. & Form Boyer's # 4		Place Chautaugus		County Chautaugus		State KANSAS		
Depth of Well 2089	Depth of Job 2079	Casing <input checked="" type="checkbox"/> New <input type="checkbox"/> Used	Size 5 1/2	Weight 15.5	Size of Hole Ann. and Kind of Cement	Cement Left in casing by	Request Necessity	feet
Kind of Job Longstring					Drillpipe	Tubing		Truck No. 25

Price Reference No. # 1
Price of Job 665.00
Second Stage
Mileage 30 67.50
Other Charges
Total Charges 732.50

Remarks **Safety Meeting, Rig up TO 5 1/2 CASING,
BREAK circulation w/ 20 Bbl Fresh water Mix
200 SK's 60/40 Pozmix 6% Gel 1/4 lb Floccle Per/SK
TAIL IN w/ 140 SK's Thickset w/ 1/4 lb
Floccle Per/SK. SHUT DOWN, WASH OUT Pump + Lines
Release Plug, DISPLACE w/ 49.5 Bbl water. Final
Pump PSI 800[#] Bump Plug to 1200[#] check FLUAT
FLUAT Held. GOOD cement Returns to SURFACE
(9 Bbl slurry). Job Complete, TEAR DOWN.
NOTE'S ROTATE casing During cement Job. GOOD circulation**

Cementor **Russell McCoy/Brad** **AT ALL TIMES During cementing Procedure**

Helper **Rick-Alan-Gary** District **EUREKA** State **KANSAS**

The above job was done under supervision of the owner, operator, or his agent whose signature appears below.

Thank you **called by Big Ed**
Agent of contractor or operator

Sales Ticket for Materials Only

Quantity Sacks	BRAND AND TYPE	RECEIVED	PRICE	TOTAL
200	SK's 60/40 Pozmix	JUN 01 2004 KCC-WICHITA	6.50	1300.00
1000 #	Gel 6%		9.50	95.00
50 #	Floccle 1/4 lb Per/SK		1.00	50.00
140	SK's Thickset (TAIL IN cement)		10.75	1505.00
35	lb's Floccle 1/4 lb Per/SK		1.00	35.00
3	hr 80 Bbl VAC Truck		65.00	195.00
1	LOAD city water (used to mix cement)		20.00	20.00
1	5 1/2 AFU FLUAT shoe		160.00	160.00
2	5 1/2 Centralizers		28.00	56.00
1	5 1/2 TOP Rubber Plug		40.00	40.00
Plugs	340 SK's	Handling & Dumping	50	170.00
	15.1 Ton	Mileage 30	80	362.40
		Sub Total		4120.90
Delivered by Truck No. # 16-29 #		Discount		
Delivered from EUREKA		Sales Tax	63	297.45
Signature of operator Russell McCoy		Total		4418.35