

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19045-00-01
Spot: N2N2NE Sec/Twnshp/Rge: 15-17S-4E
4824 feet from S Section Line, 1381 feet from E Section Line
Lease Name: ED RIFFEL Well #: 3
County: MARION Total Vertical Depth: 2390 feet

Operator License No.: 5192
Op Name: SHAWMAR OIL & GAS CO., INC.
Address: 1116 E MAIN PO BOX 9
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2353		40 SX
SURF	8.625	127		93 SX

\$ 77.68

Well Type: EOR UIC Docket No: E26622.1 Date/Time to Plug: 03/01/2007 12:00 AM
Plug Co. License No.: 33307 Plug Co. Name: FLINT HILLS OIL CO., LLC
Proposal Rcvd. from: BEAU J. CLOUTIER, PRESI Company: SHAMWAR OIL & GAS CO., INC. Phone: (620) 382-2932

Proposed
Plugging
Method:

Sand to 2,300' & top with 4 sxs. cement. Perforate 4 1/2" casing 250' & circulate cement to surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL
Date/Time Plugging Completed: 07/03/2007 11:30 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Sanded to 2,300' & topped with 4 sxs. cement. 8 5/8" X 4 1/2" annulus squeezed from 231' to 0' per Alt. I requirements. Pumped 37 sxs. cement from 260' to surface inside 4 1/2" casing.

INVOICED
DATE 8-3-07
INV. NO. 2008060225

Remarks: USED 60/40 POSMIX W/4% GEL BY CONSOLIDATED OILWELL SERVICES, LLC. INVOICE #17207.

Plugged through: CSG

District: 02

Signed

Michael R Wilson

(TECHNICIAN)

PPT