

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22404-00-00
Spot: SWSENW Sec/Twnshp/Rge: 2-18S-7W
2970 feet from S Section Line, 3526 feet from E Section Line
Lease Name: WHITE A Well #: 2
County: RICE Total Vertical Depth: 3320 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N. PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3319		150 SX CMT
SURF	8.625	224		150 SX CMT
T1	2.375	3254		

\$ 107.90

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2007 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: SAND PERFS TO 3050' & CAP WITH 4 SX'S CEMENT, CUT OFF CASING & PULL TO 1050' & PUMP 35 SX'S, PULL CASING TO 650' & PUMP 35 SX'S, PULL CASING TO 275' & CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: BILL JOHNSON Witness Type: NONE
Date/Time Plugging Completed: 07/18/2007 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 3050' & CAP WITH 4 SX'S CEMENT, CUT CASING @ 1122' & PULL TO 1050' & PUMP 35 SX'S, PULL CASING TO 650" & PUMP 35 SX'S, PULL CASING TO 275' & CIRCULATE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3224	3231		
3104	3111		

INVOICED

DATE 8-6-07
INV. NO. 2008060228

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #32083. USED 220 SX'S TOTAL & 200 LBS COTTON HULLS.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION CP-2/3

AUG 01 2007

CONSERVATION DIVISION
WICHITA, KS

PKT