

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-27486-00-00
Spot: NWNESE Sec/Twnshp/Rge: 3-26S-18E
1155 feet from S Section Line, 495 feet from E Section Line
Lease Name: N FINNEY Well #: 12
County: ALLEN Total Vertical Depth: 800 feet

Operator License No.: 33221
Op Name: ROXANNA PIPELINE, INC.
Address: 4600 GREENVILLE AVE., SUITE 200
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	800	0	
SURF	7	20	0	

\$ 35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2004 12:00 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: TOM GILBERT Company: ROXANNA PIPELINE, INC. Phone: (214) 691-6216

Proposed Plugging Method: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 07/21/2007 12:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PLUGGED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 650 PSI. 28 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

INVOICED
DATE 8-3-07
INV. NO. 2008060223

RECEIVED
KCC DISTRICT #3

JUL 25 2007 CPT

CHANUTE, KS

Remarks: THIS WELL WAS GPS'ED AS NO. NFI 21 AT 1133' NSL & 534' WEL OF S.3.

Plugged through: CSG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

JUL 30 2007

CONSERVATION DIVISION
WICHITA, KS

PRT