

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22445-00-00  
Spot: SENENE Sec/Twnshp/Rge: 13-21S-9W  
4530 feet from S Section Line, 260 feet from E Section Line  
Lease Name: AXTELL B Well #: 1  
County: RICE Total Vertical Depth: 3440 feet

Operator License No.: 5210  
Op Name: LEBSACK OIL PRODUCTION, INC.  
Address: 205 E 7TH ST HADLEY CTR BOX 489  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3435		150 SX
SURF	8.625	284		240 SX

\$ 111.80

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/25/2007 12:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/25/2007 2:30 PM KCC Agent: VIRGIL CLOTHIER

**Actual Plugging Report:**

SAND PERFS TO 3230' AND CAP WITH 5 SX'S CEMENT, CUT OFF CASING @ 2320' AND PULL TO 1150' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS, PULL CASING TO 700' AND PUMP 35 SX'S CEMENT WITH 100#'S COTTON HULLS, PULL CASING TO 334' AND CIRCULATE CEMENT TO SURFACE.

**Perfs:**

Top	Bot	Thru	Comments
3302	3322		

INVOICED

DATE 8-6-07  
INV. NO. 2008060230

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET C-32153. USED 220 SX'S.

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

AUG 01 2007

CONSERVATION DIVISION  
WICHITA, KS

*PT*