

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21861-00-00
Spot: SENESE Sec/Twnshp/Rge: 23-19S-6W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: IHDE Well #: 2-23
County: RICE Total Vertical Depth: 3407 feet

Operator License No.: 33288
Op Name: MANNING, GREGORY
Address: 574 SE 130 AVE.
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3393		175 SX
SURF	8.625	215		175 SX

\$ 110.73

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/27/2007 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE
Date/Time Plugging Completed: 07/27/2007 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 3275' & CAP WITH 4 SX'S CEMENT, CUT OFF CASING @ 2000' & PULL TO 800' & PUMP 35 SX'S CEMENT, PULL CASING TO 450' & PUMP 35 SX'S CEMENT, PULL CASING TO 270' & CIRCULATE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3336	3340		
3326	3330		

INVOICED
DATE 8-6-07
INV. NO. 2008060231

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-32463. USED 195 SX'S TOTAL.

AUG 03 2007

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

PT