

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23700-00-00
Spot: NWNESW Sec/Twnshp/Rge: 16-26S-5E
2314 feet from S Section Line, 3680 feet from E Section Line
Lease Name: KOGLER A Well #: 300
County: BUTLER Total Vertical Depth: 2437 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2432		200/125 SX CMT. # 79.20
SURF	8.625	255		150 SX CMT.
T1	2.375	2434		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2007 8:00 AM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2007 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

5-17-2007 RIH W/TBG @ 2395', UNITED CEMENTING MIXED & PUMPED 50 SXS CLASS A 3% CC. WAITED 2 HOURS, TAGGED CEMENT @ 2151', PRESSURED CSG @ 300#, HELD OK. RIH W/TBG @ 315', UNITED CEMENTING MIXED & PUMPED 35 SXS 60/40 POZ MIS 4% GEL TO SURFACE. CEMENT CIRCULATED, PUMPED 2 SXS ON BACKSIDE OF 5-1/2" CSG. TO FILL TO SURFACE. P & A COMPLETE 1300, 05-17-2007. UNITED CEMENTING TICKET #7902.

Perfs:

Top	Bot	Thru	Comments
2428	2434		

INVOICED
DATE 8-6-07
INV. NO. 2008060235

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 03 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: -096.89271.37.78721

Plugged through: TBG

District: 02

Signed Duane R. Krueger
(TECHNICIAN)