

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-05562-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 26-11S-17W  
990 feet from S Section Line, 990 feet from E Section Line  
Lease Name: MCCORD A Well #: 12  
County: ELLIS Total Vertical Depth: 3569 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PARKWAY, BLDG  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3562	0	125 SX
SURF	8.625	360	0	150 SX

\$ 115.99

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/11/2007 9:30 AM  
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed  
Plugging  
Method:

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/11/2007 11:35 AM KCC Agent: BRUCE BASYE

**Actual Plugging Report:**

Well squeezed at 940' w/600 sxs; 832' - 853' w/250 sxs.  
Tubing at 3500' - pumped 135 sxs 60/40 pozmix - 10% gel with 800# hulls.  
Pulled tubing to 1500' - pumped 110 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Pulled tubing - pumped 25 sxs 60/40 pozmix - 10% gel down 8 5/8" x 5 1/2" annulus.  
Max. P.S.I. #100.  
Tied onto 5 1/2" casing - 20 sxs down 5 1/2".

**Perfs:**

Top	Bot	Thru	Comments
3562	3569		OH

**INVOICED**  
DATE 0-22-07  
INV. NO. 2007061938

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

*Bruce Basye*

(TECHNICIAN)

RECEIVED

KANSAS CORPORATION COMMISSION

JUN 18 2007  
Form CP-2/3  
CONSERVATION DIVISION  
WICHITA, KS

JUN 14 2007

*PK*

CITIES SERVICE OIL CO

#12 McCORD

26-11-17W  
NW SE SE

Contr.

ELLIS County

E 210<sub>1</sub>

Comm. 11-5-41

Comp. 12-17-41

IP


3000 BOPD

ECHO

Tops	Depth	Datum
ANH	1265	
ARB	3561	
TD	3569	

Casing  
5" 3561

2775' OIL/1 hr @ 3569



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS