

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-27045-00-00  
Spot: NWSE Sec/Twnshp/Rge: 14-25S-13E  
2185 feet from S Section Line, 2048 feet from E Section Line  
Lease Name: NORDMEYER Well #: 2  
County: WOODSON Total Vertical Depth: 1525 feet

Operator License No.: 6788  
Op Name: NORDMEYER OIL, INC.  
Address: 362 90TH RD  
TORONTO, KS 66777

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	40	0	15 SX

\$ 49.56

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/27/2006 1:30 PM  
Plug Co. License No.: 30567 Plug Co. Name: RIG 6 DRILLING CO., INC.  
Proposal Rcvd. from: RIG 6 DRILLINS CO.INC. Company: RIG 6 DRILLING CO., INC. Phone: (620) 365-6294

Proposed Plugging Method: PUT IN 15 SACKS OF 60/40 POZMIX CEMENT THROUGH DRILL PIPE 1525 FT. PULLED PIPE 493 FT. RAN 15 SACKS IN KANSAS CITY ZONE. 55 SX 250 FT. TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE  
Date/Time Plugging Completed: 06/27/2006 4:15 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THIS WELL CONSISTED OF AN UNCASSED BORE TO 1525'. DRILL PIPE WAS RAN INTO THE WELL TO 1525'. 15 SACKS OF CEMENT WERE PUMPED THROUGH THE DRILL PIPE TO T.D.. THE DRILL PIPE WAS PULLED TO 493' AND 15 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE DRILL PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE DRILL PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE DRILL PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 85 SACKS OF CEMENT WERE PUMPED INTO THIS WELL

Perfs:

RECEIVED  
KCC DISTRICT #3  
JUN 13 2007 CPT  
CHANUTE, KS

INVOICED  
DATE 6-22-07  
INV. NO. 2007061934

Remarks:  
Plugged through: DP

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

JUN 18 2007

CONSERVATION DIVISION  
WICHITA, KS

*RT*