

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24320-00-00
Spot: SWNWNWSW Sec/Twnshp/Rge: 2-21S-19E
2030 feet from S Section Line, 5055 feet from E Section Line
Lease Name: HOWARD BENJAMIN Well #: S-2
County: ANDERSON Total Vertical Depth: 792 feet

Operator License No.: 3728
Op Name: KENT, ROGER DBA R J ENTERPRISES
Address: 1203 E. 4TH AVE.
GARNETT, KS 66032

String Size Depth (ft) Pulled (ft) Comment
SURF 7 20

\$ 35.00

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/15/2006 8:00 AM
Plug Co. License No.: 3728 Plug Co. Name: KENT, ROGER DBA R J ENTERPRISES
Proposal Rcvd. from: ROGER KENT Company: KENT, ROGER DBA R J ENTERPRIS Phone: (785) 448-6995

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 782'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT TD., TO PLACE A 50' CEMENT PLUG AT 500' AND TO PLACE A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: LARRY MARCHANT Witness Type: NONE
Date/Time Plugging Completed: 06/15/2006 12:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE WELL TO 775'. 12 SACKS OF CEMENT WERE PUMPE THROUGH THE 1" PIPE TO 775'. THE PIPE WAS PULLED TO 500' AND 12 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE 1" PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 60 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Perfs:

RECEIVED
KCC DISTRICT #3

JUN 13 2007

CPT

CHANUTE, KS

INVOICED

DATE 6-22-07

INV. NO. 2007061935

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P Titel
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

JUN 18 2007

CONSERVATION DIVISION
WICHITA, KS

PCT