


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rooks County. Sec. 20 Twp. 10S Rge. 17 (W) W (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Davis Bros. - Transit Corporation  
Lease Name Burton Well No. 1  
Office Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) D and A  
Date well completed July 23, 1958  
Application for plugging filed July 23, 1958  
Application for plugging approved July 23, 1958  
Plugging commenced July 23, 1958  
Plugging completed July 23, 1958  
Reason for abandonment of well or producing formation No production

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	175'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy drilling mud to 600; set plug with 20 sacks cement.  
Filled hole with heavy drilling mud to 165; set plug with 1/2 sack hulls and 15 sacks cement  
Filled hole with heavy drilling mud to 40; set plug with 1/2 sack hulls and 10 sacks cement to bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation  
Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.  
Paul E. Gathers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul E. Gathers

SUBSCRIBED AND SWORN TO before me this 18<sup>th</sup> day of August, 1958 (Address)

My commission expires May 17, 1962 Mildred Jean Notary Public.

PLUGGING  
FILE SEC. 20 T. 10 R. 17W  
BOOK PAGE 120 LINE 9

08-25-1958

15-163-00766-00-00

DRILLER'S WELL LOG

Davis Bros.-Transit Corporation - Burton # 1 located in  
NE NE NE Sec. 20-10S-17W,  
Rooks County, Kansas

Commenced: July 10, 1958  
Completed: July 23, 1958  
Elevation: 2105' K.B.

Casing 8 5/8" @ 175'  
Cemented w/125 sacks

<u>Formation</u>	<u>From</u>	<u>To</u>
Clay and sand	0	75
Shale and shells	75	150
Shale	150	175
Shale and shells	175	890
Sand	890	1200
Shale and sand streaks	1200	1380
Anhydrite	1380	1415
Shale and shells	1415	1980
Shale and lime	1980	2160
Lime and shale	2160	2385
Shale and lime	2385	2560
Lime and shale	2560	2770
Shale and lime	2770	2925
Lime and shale	2925	3045
Shale and lime	3045	3090
Lime and shale	3090	3135
Shale and lime	3135	3200
Lime and shale	3200	3335
Lime	3335	3585
Lime and cherty conglomerate	3585	3654
Conglomerate and chert	3654	3666
Cherty conglomerate	3666	3724
Arbuckle lime	3724	3746 TD

Summary of Formation

Topeka	3065'
Heebner	3287'
Toronto	3308'
Lansing	3328'
K. C. Base	3563'
Conglomerate	3603'
Simpson Dolo.	3675'
Arbuckle	3710'

I hereby certify the foregoing to be a true and accurate Driller's Log of the formation encountered in the above well.

Subscribed and sworn to before me  
this 18th. day of August, 1958.

My Commission expires May 17, 1962.

TRANSIT CORPORATION

By Paul E. Gathers

Midred Tom

PLUGGING  
 FILE SEC. 20 T. 10 R. 17W  
 BOOK PAGE 120 LINE 9

RECEIVED  
 STATE DEPARTMENT  
 08-25-1958