


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas



Locate well correctly on above Section Plat

Rooks County. Sec. 33 Twp. 10S Rge. 17W(E) (W)  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE  
Lease Owner ALPINE OIL & ROYALTY CO., INC.  
Lease Name BRUMITT Well No. 1  
Office Address 800 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed April 27, 1963 19  
Application for plugging filed April 27, 1963 19  
Application for plugging approved April 27, 1963 19  
Plugging commenced April 27, 1963 19  
Plugging completed April 27, 1963 19  
Reason for abandonment of well or producing formation non-productive in commercial quantities  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3680 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	320'	cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud from Total Depth 3680 feet to surface between each plug No. 1 Plug at 550 and 20 sacks cement - No. 2 plug at 240 feet and 20 sacks cement - No. 3 plug at 40 feet and 10 sacks cement - 2 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 3 1963  
05-03-1963  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Halliburton and Quaker Drilling Co., Inc.  
Address 800 Bitting Building, Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Thomas M. McCaul (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul  
800 Bitting Building, Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of May 1963

My commission expires August 10, 1965

Virginia Marshall  
Notary Public.

15-163 01082 -00-00

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: April 17, 1963

Contractor: Quaker Drilling Co., Inc.

Completed: April 27, 1963

No. 1 Brumby  
NE NE NE Sec. 33, 10S-17E  
Rooks County, Kansas

Elevation: 2078 X. B.

Casing Record

Set 3 5/8 inch casing at 320 feet with 225 sacks of cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Chalky post rock	80	Topeka	3022 - 944
Sticky blue shale	195	Heebner	3245 -1167
Shale	320	Toronto	3264 -1186
Shale and Shells	400	Lansing	3287 -1209
Shale, Shells & Clay	620	Base of Kansas City	3545 -1467
Dakota Sand	970	Conglomerate	3587 -1509
Shale and Shells	1315	Simpson	3655 -1577
Red Bed	1305	Arbuckle	3663 -1585
Anhydrite	1355	Rotary Total Depth	3680 -1602
Shale and Shells	1580		
Lime and Shale	1630		
Shale and Shells	1870		
Lime and Shale	2325		
Cherty Lime	2375		
Lime	2425		
Cherty Lime and Shale	2480		
Lime	2565		
Cherty Lime and Cherty Shale	2621		
Lime and Shale	2630		
Lime	2680		

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAY 3 1963  
05-03-1963  
CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the Driller's Log of the well as filed in the NE NE NE of Section 33, Township 10 South, Range 17 West, Rooks County, Kansas.

QUAKER DRILLING CO., INC.

By: Thomas M. McCaul  
Thomas M. McCaul

SUBSCRIBED AND SWORN TO before me a Notary Public this 1st day of May, 1963.

Virginia Mundell  
Virginia Mundell, Notary Public

MY COMMISSION EXPIRES:  
August 10, 1965