

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas


WELL PLUGGING RECORD

15-103-19357-00-00

Rooks County. Sec. 32 Twp. 10S Rge. 17 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW  
Lease Owner Tennessee Gas Transmission Company  
Lease Name Ridler "K" Well No. 2  
Office Address P. O. Box - Chase, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 3-13 1957  
Application for plugging filed 3-14 1957  
Application for plugging approved 3-13 1957  
Plugging commenced 3-13 1957  
Plugging completed 3-13 1957  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Arbuckle (test) Depth to top 3512 Bottom \_\_\_\_\_ Total Depth of Well 3592 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8" OD	1211	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled w/heavy mud to 450'

Set plug @ 450'

Ran 20 sax cement through drill pipe, filled to 40'

Set plug @ 40' w/ 1/3 sack of hulls

Cemented to surface w/10 sax cement.

03-14-1957

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF Kansas, COUNTY OF Rice, ss.  
Glen E. Armour (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Glen E. Armour

(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of March, 1957

Clarence O. Gray  
Notary Public.

My commission expires May 20, 1958



15-163-19357-00-00

COMPANY: Tennessee Gas Transmission Company  
Chase, Kansas

Rotary Drilling Commenced: 2-27-57  
Rotary Drilling Completed: 3-13-57

LOCATION: Ridler "K" #2  
SW SW SW 32-108-17W  
Rocks County, Kansas

CONTRACTOR: Shelley-Miller Drilling Company  
205 Miller Building  
Wichita, Kansas

CASING RECORD: 8 5/8" 24# steel casing set @ 1211' cemented  
with 600 sacks cement

L O G  
(Measurements from top of Rotary Bushing to bottom  
of formation)

Ground L. to Kelly	4
Post Rock	35
Sand	50
Shale & Shells	680
Sand	850
Red Bed	885
Red Bed & Pyrite	1,190
Red Bed	1,206
Anhydrite	1,235
Red Bed	1,250
Shale & Shells	1,760
Line & Shale	2,755
Line	3,532
Dolomite	3,593 Rotary T.D.

The undersigned, Richard A. Shelley, Partner of Shelley-Miller Drilling Company, hereby certifies in behalf of said company, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

SHELLEY-MILLER DRILLING COMPANY

*Richard A. Shelley*

STATE OF KANSAS }  
COUNTY OF SEDGWICK } SS

BE IT REMEMBERED, that on this 21st day of March, 1957, before me, the undersigned, a Notary Public, duly commissioned in and for the county and state aforesaid, came Richard A. Shelley, Partner, and known to me to be the same person who executed the foregoing instrument of writing in behalf of Shelley-Miller Drilling Company, as a Partner of said company, and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

*Leon M. Lowers*  
Notary Public

My Commission Expires:  
March 24, 1960

FILED  
MARCH 21 1957  
SEDGWICK COUNTY, KANSAS

PLUGGING  
FILE SEC. 32 T. 10 R. 17W  
BOOK PAGE 148 LINE 32

(2) Chase file -  
2-10  
1-10  
1-10