


15-163-00566-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 29 Twp. 10S Rge. (E) 17(W)
Location as "NE/CNW/SW" or footage from lines SW SE SW
Lease Owner Earl F. Wakefield & A. B. Chadwick
Lease Name Kaba Well No. 1
Office Address 307 Union Nat'l Bank Bldg., Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 12 19 53
Application for plugging filed February 13 19 53
Application for plugging approved " " 19 53
Plugging commenced " " 19 53
Plugging completed " " 19 53
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3611 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 101 | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3611 feet to 150 feet, Halliburton Plug 1/2 half sack hulls at 150 feet cemented with 20 sacks, mud to 40 feet, Halliburton plug & 1/2 sack hulls at 40 feet, cemented to bottom of cellar with 10 sacks cement.

02-17-1953

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Earl F. Wakefield
Address 307 Union Nat'l Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Earl F. Wakefield (employee or owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield
307 Union Nat'l Bank Bldg.
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of February, 19 53

My commission expires 12-23-54

24-2675-S 2-52-20M



Notary Public.

15-163-00566-00-00

Kaba #1
Owners: Earl F. Wakefield & A. B. Chadwick
Contractor: Earl F. Wakefield
Comm 2/2/53 Comp: 2/13/53

SW SE SW 29-10S-17W
Rooks County, Kansas
Casing: 101' of 8 5/8"

Elevation: 1994 D.F.

| | |
|-----------------------|------|
| Surface | 101 |
| Blue Sticky Shale | 530 |
| Dakota Sand | 616 |
| Shale, Sand & Red Bed | 1162 |
| Shale & Red Bed | 1258 |
| Anhydrite | 1315 |
| Shale | 1892 |
| Shale & Shells | 2010 |
| Lime & Shells | 2165 |
| Lime & Shale | 2241 |
| Shale | 2330 |
| Lime & Shells | 2435 |
| Lime & Shale | 2580 |
| Shale | 2660 |
| Lime & Shale | 2842 |
| Shale | 2980 |
| Lime & Shale | 3525 |
| Chert & Lime | 3550 |
| Cherty Conglomerate | 3594 |
| Arbuckle Lime | 3611 |
| Total Depth | 3611 |

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby agree and certify that the above is a true and correct copy of the log on the Kaba #1 well located SW SE SW 29-10S-17W, Rooks County, Kansas.

Earl F. Wakefield

Subscribed and sworn to before me this 16th day of February, 1953.

B. Jeanne Gaffney
Notary Public

My Commission Expires: 12-23-54

