

15-163-20057-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Rooks \_\_\_\_\_ County. Sec. 27 Twp. 10 Rge. \_\_\_\_\_ (E) 17 (W)  
Location as "NE/CNW/SW" or footage from lines SE SW NW  
Lease Owner Allison & Black  
Lease Name Schrandt Well No. 1  
Office Address 1415 Wichita Plaza - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry  
Date well completed 12-3- 1967  
Application for plugging filed 12-3 1967  
Application for plugging approved 12-3 1967  
Plugging commenced 4:00 AM 12-3 1967  
Plugging completed 8:45 AM 12-3 1967  
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey - Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3400 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Soil Sand Shale		0	169	12 1/4	169	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole - Cemented with 100 sacks at 720' 25 sacks at 180' and 40' with 10 sacks - 2 sacks in rat hole plugged by Leo Massey - Hays, Kansas by Globe Pump Truck

RECEIVED  
DEC 5 1967  
12-05-1967  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor B & B Drilling, Inc.  
Address 548 Petroleum Building - Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss. Bill Lahar (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar  
548 Petroleum Building - Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of DECEMBER, 19 67

My commission expires May 31, 1970

Alma A. Meiser  
Notary Public.

# B & B DRILLING, INC.

548 Petroleum Building

Wichita, Kansas 67202

December 4, 1967

15-163-20057-00-00

## DRILLERS LOG

Re: Schrandt #1

SE SW NW Sec. 27-10S-17W

Rooks County, Kansas

COMPANY: Allison & Black  
CONTRACTOR: B & B Drilling, Inc.  
TOTAL DEPTH: 3400'  
COMMENCED: November 27, 1967  
COMPLETED: December 3, 1967

0	168	Soil & Sand
168	220	Shale
220	1110	Shale & Sand
1110	1316	Shale
1316	1350	Anhydrite
1350	1540	Shale
1540	1920	Shale & Lime
1920	2190	Shale & Lime
2190	2370	Shale & Lime
2370	2481	Lime & Shale
2481	2745	Shale & Lime
2745	2910	Shale & Lime
2910	2940	Lime & Shale
2940	3110	Lime & Shale
3110	3220	Lime & Shale
3220	3255	Lime
3255	3378	Lime & Shale
3378	3400	Lime & Shale
3400		Total Depth

DST #1  
D & A

RECEIVED  
DATE CORRECTED 01/11/1968  
DEC 5 1967  
12-05-1967  
CONSERVATION DIVISION  
Wichita, Kansas

We certify the above and foregoing to be true and correct copy of the log on the #1 Schrandt, located in Rooks County, Kansas

Bill Lohar

President

Oliver G. Meiser

Notary Public

Subscribed and sworn to before me this 4th day of December, 1967

My commission expires May 31, 1970