

15-163-00630-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 27 Twp. 10 Rge. 17 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner Trans Era Petroleum, Inc.

Lease Name Colby Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 2/15/53 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 6/14/53 19

Plugging completed 6/17/53 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production June 13, 1953 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3678 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	182	None
				5 1/2"	3675 1/2	2781

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING RECORD

Plugged back with crushed rock to 3360', dumped 4 sax cement at 3360' with dump bailer. top of cement 3330'. Filled hole with mud to 180'; set rock bridge, dumped 15 sx cement, top of cement 135'. Filled with mud to 35', set rock bridge, dumped 10 sax cement for cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Herbert R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. R. Michaelis*
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of June, 19 53

My commission expires 1-30-57.

Margie Cooper
Notary Public.

PLUGGING
FILE SEC 27 T 10 R 17 W
BOOK PAGE 106 LINE 25

24-7366-S 3-53-20M

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1953
06-30-53
CONSERVATION DIVISION
Wichita, Kansas

Trans Era Petroleum, Inc.
Colby #1

NE NE SW 27-10-17
Rooks County, Kans.

Total Depth: 3678'
Comm. 1/31/53
Comp. 2/15/53

Casing

Cement

8 5/8" set @ 182'
5 1/2" Set @ 3675 1/2'

135 sacks Lone Star
135 sacks Lone Star

Formation	Depth
Surface formations	75
Shale-sand	183
Shale-shells	442
Shale	660
Iron	665
Sand-shale	785
Shale-shells	880
Sand	960
Sand-shale	1045
Red bed-shale	1315
Anhydrite	1350
Shale-shells-red bed	1615
Shale-shells-lime	1850
Shale-lime	3227
Lime	3590
Conglomerate	3637
Simpson	3652
Shale	3670
Arbuckle	3678'

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Cora Betz

Subscribed and sworn to before me this 19th day of February, 1953.

Margie Cooper
Notary Public

My commission expires: 1-30-57.

