

*Mock*

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas

15-163-20061-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rocks \_\_\_\_\_ County. Sec. 21 Twp. 10 Rge. 17 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines SE NW NW  
Lease Owner DAVIS BROS.  
Lease Name Mock "A" Well No. 1  
Office Address 500 McFarlin Building Tulsa, Oklahoma 74103  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed September 24, 19 67  
Application for plugging filed January 14 19 71  
Application for plugging approved January 15 19 71  
Plugging commenced January 26 19 71  
Plugging completed January 26 19 71  
Reason for abandonment of well or producing formation Well in waterflood  
flooded out and went to water.  
If a producing well is abandoned, date of last production September 30 19 70  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Kansas City Depth to top 3445 Bottom 3541 Total Depth of Well 3595 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City	Water	3541	Surface	4 1/2	3593	None
	Casing was squeezed at	730'	with	250 sx. cement		
				8 5/8	150	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from Surface feet to 3539 feet for each plug set.

Pumped 50 sacks 60/40 Poz mix cement down annulus to plug surface.  
Pumped through 4 1/2" plug container with 50 sacks 60/40 Poz mix with 6 sacks of hulls--Pumped 22 sacks of Gel.  
Released plug and pumped 55 sacks 60/40 Poz mix cement to 550'. Well squeezed at 2000 P.S.T. - Shut in pressure.  
Plugging completed.  
Cement plug from 3446' to 3539' (Perfs.)  
Gel plug from 550' to 3446'  
Cement plug from surface to 550'  
Halliburton Top plug set at 550'

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
02-12-1971

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services  
Address Hays, Kansas

STATE OF Oklahoma, COUNTY OF Tulsa, ss.  
Ralph A. Hockenson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph A. Hockenson  
500 McFarlin Building Tulsa, Oklahoma 74103  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of February, 19 71

Patricia B. Springfield  
Notary Public.

My commission expires March 20, 1974

15-163-20061-00-00

COMPANY  
CONTRACTOR  
FARM  
LOCATION

Davis Brothers  
LEBEN DRILLING, INC.  
MOCK A-1  
SE NW NW Section 21-10s-17w  
Rooks County, Kansas  
9-12-67  
9-18-67

COMMENCED  
COMPLETED

0-	60	Clay, Sand, Post Rock
60	100	Post Rock
100	680	Shale
680	1070	Sand, Shale
1070	1346	Red Bed and Shale
1346	1378	Anhydrite
1378	1650	Shale
1650	1965	Shale and Shells
1965	2340	Lime and Shale
2340	2560	Shale
2560	3095	Shale and Shells
3095	3165	Shale and Lime
3165	3595	Lime
	3595	RTD - Set 4½" Casing

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
02-12-1971

8 5/8" New Surface Casing - Set @ 150' with 135 sx Common cement  
2% cc - Cement Circulated

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Mock A-1, located SE NW NW of Section 21, Township 10 South, Range 17 West, Rooks County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite  
Leslie Kite

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 21st day of September, 1967.

Ulanda Nichols  
Ulanda Nichols, Notary Public

My Commission Expires - April 1, 1971