

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Herman L Loeb  
Address: PO Box 524 Lawrenceville, Illinois  
Phone: (618) 943-2227 Operator License #: 3273  
Type of Well: OIL Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: June 18, 2007 (Date)  
by: Pat Bedore (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Lansing Depth to Top: 3334 Bottom: 3340 T.D. 3595  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-039200840000  
Lease Name: Sumner XB PFT 7/30/07  
Well Number: 1 PER T-1  
~~Is SWD~~ Spot Location (QQQQ): nesw - SW - SW KCC  
634 Feet from  North /  South Section Line PFT  
4900 Feet from  East /  West Section Line per  
Sec. 4 Twp. 1 S. R. 26  East  West 6 PS  
County: Decatur 7/30/07  
Date Well Completed: May 13, 1969  
Plugging Commenced: June 18, 2007  
Plugging Completed: June 18, 2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0	258	8 5/8"		None
	Production	0	3595	4 1/2"		None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 1980', pumped 50 sacks of 60/40 Poz w/10% Gel cement w/200#'s of hulls down tubing. Pulled tubing to 1400', pumped 60 sacks of cement w/200#'s of hulls to surface. Pulled tubing, topped off casing w/25 sacks of cement. pumped 65 sacks of cement down backside @ 100#'s pressure. Plug down @ 12:30 pm.

Name of Plugging Contractor: Ultimate Well Service License #: 33771  
Address: Ellis, KS  
Name of Party Responsible for Plugging Fees: Herman L Loeb  
State of Illinois County, Lawrence, ss.  
Roland Nyp (Employee of Operator) or (Operator) on above-described well, being first duly

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 26 2007  
CONSERVATION DIVISION  
WICHITA, KS

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Roland Nyp

(Address) 804 Main Stockton, KS 67669



SUBSCRIBED and SWORN TO before me this 25<sup>th</sup> day of July, 2007

Steve R Nyp My Commission Expires: 9-30-2008  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten initials]*