

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

JUL 23 2007

CONSERVATION DIVISION
WICHITA, KS

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior, Inc.
Address: P.O. Box 399
Phone: (785) 398-2270 Operator License #: 4058
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 07/19/2007 (Date)
by: Mike Maier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippian Depth to Top: 4341' Bottom: 4344' T.D. 4344'

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 135-24009 - 00-00
Lease Name: Beltz
Well Number: 1
Spot Location (QQQQ): _____ - SW - NW - NW
990 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 29 Twp. 20 S. R. 21 East West
County: Ness
Date Well Completed: 09/01/1997
Plugging Commenced: 07/19/2007
Plugging Completed: 07/19/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippian	Water & Oil	4340'	4344'	8 5/8"	210'	None
				5 1/2"	4341'	None


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Swift Services pumped 35 sacks of 60/40 poz, 6% gel with 200# of hulls and 8 sacks of gel and well pressured up to 3000 psi.
H-D Oil Field Service rig ran tubing to 1400' and Swift Services mixed 130 sacks of 60/40 poz, 6% gel and circulated to surface.
Pulled tubing out and filled up casing with 35 sacks of 60/40 poz, 6% gel. Well plugged.

Name of Plugging Contractor: Swift Services, Inc License #: 32382
Address: N Highway 283, Ness City, KS 67560

Name of Party Responsible for Plugging Fees: American Warrior, Inc.
State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
(Signature) [Signature]
(Address) 210 W Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 19th day of July, 20 07



Bernice Moore My Commission Expires: 2/7/10
Notary Public

AGT