

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

RECEIVED
 KANSAS CORPORATION COMMISSION
 OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
 K.A.R. 82-3-117

Form CP-4
 December 2003
 Type or Print on this Form
 Form must be Signed
 All blanks must be Filled

JUL 23 2007

CONSERVATION DIVISION
 WICHITA, KS

Lease Operator: R & B Oil & Gas, Inc.
 Address: PO Box 195, Attica, KS 67009
 Phone: (620) 254-7251 Operator License #: 31191
 Type of Well: Gas Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: _____ (Date)
 by: Doug Louis (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Topeka Depth to Top: 2891 Bottom: 3057 T.D. 3057
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 077-21423-0000
 Lease Name: Bertholf
 Well Number: 2 A
 Spot Location (QQQQ): _____ - SW - NW - NE
950 Feet from North / South Section Line
2240 Feet from East / West Section Line
 Sec. 24 Twp. 31S S. R. 9 East West
 County: Harper
 Date Well Completed: 1-30-02
 Plugging Commenced: 05-02-07
 Plugging Completed: 05-03-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	221	
<u>Topeka</u>	<u>Gas</u>			4 1/2	3055	1910


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tried to blow gas off, water started coming, blew well for 1 1/2 hours, pumped 35 sacks cement down to 2400', had 1700 psi, shut in, let set for two hours, blew gas off casing, set floor, pulled slips, ripped casing at 2050', worked pipe, ripped casing at 1910', came free, pulled up to 1500', pumped 35 sacks, pulled up to 900', surface was gasing, pumped 60 sacks hot cement, pulled up to 270', circulated with 150 sacks, pulled rest of casing.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
 Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: R & B Oil & Gas, Inc.
 State of KANSAS County, HARPER, ss.

R & B Oil & Gas, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Randy Neuberry
 (Address) President PO Box 195, Attica, KS 67009

SUBSCRIBED and SWORN TO before me this 20th day of July, 2007

Jane Swingle My Commission Expires: 1-6-2011
 Notary Public, Jane Swingle

PPT