

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Berexco, Inc.  
Address: PO Box 723 Hays, KS 67601  
Phone: (785) 628-6101 Operator License #: 5363  
Type of Well: SWD EOR KCCPKT 7/30/07 per RBDms CP2/B  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) Docket #: E-251511 E2551  
(If SWD or ENHR)  
The plugging proposal was approved on: 7-16-07 (Date)  
by: Daryl Dipman (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Cherokee Depth to Top: 4670 Bottom: 75 T.D. 4769  
Johnson Depth to Top: 4706 Bottom: 20 T.D. 4769  
KC-F / KC-I Depth to Top: 4239/4337 Bottom: 48/40 T.D. 4769

API Number: 15-109-20468-00-00  
Lease Name: REB  
Well Number: 2  
Spot Location (QQQQ): SE - NE - NW -  
4290 Feet from  North /  South Section Line  
2970 Feet from  East /  West Section Line  
Sec. 3 Twp. 12 S. R. 34  East  West  
County: LOGAN  
Date Well Completed: 12/88  
Plugging Commenced: 7-16-07  
Plugging Completed: 7-16-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
CHEROKEE	WATER	0	343'	8-5/8	12/88	----
JOHNSON	WATER	0	4768'	4-1/2	12/88	----
KC-F	WATER					
KC-I	WATER					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


TIH TO 4270' BELOW F PUTS @ 4239-48- CIBP @ 4318 MIX 125 SKS 60/40 10% GEL W/ 400# HULLS PULL TBG TO 2584' MIX 100 SKS 60/40 W/ GEL & 200 # HULLS. PULL TBG TO 1253' PUMP 40 SKS 60/40 10% GEL. TOH W/ TBG TIE ONTO 4-1/2 CSG. PUMP 20 SKS PSI TO 250# SI AT 200#.

2 sks down 8 5/8

Name of Plugging Contractor: POE SERVICING License #: 3005 3152  
Address: PO BOX 115 OBERLIN, KS 67749  
Name of Party Responsible for Plugging Fees: Mark Leiker w/ Berexco, Inc.  
State of KS County, Ellis, ss. per CP2/B

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark Leiker  
(Address) PO Box 723 Hays, KS 67601



SUBSCRIBED and SWORN TO before me this 23 day of July, 20 07  
Shanna Miller My Commission Expires: 9/19/09  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

JUL 25 2007

CONSERVATION DIVISION  
WICHITA KS