

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20790-00-00
Spot: NESWSW Sec/Twnshp/Rge: 8-10S-25W
990 feet from S Section Line, 990 feet from W Section Line
Lease Name: MCGUIRE Well #: 1
County: GRAHAM Total Vertical Depth: 4040 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4031	0	175 SX
SURF	8.625	201	0	175 SX

\$ 131.30

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/29/2007 10:00 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 500# hulls.
Squeeze jobs: 1621' - 1746' w/150 sxs; 1906' - 2020' w/175 sxs.
Fluid level 900'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/29/2007 1:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2500'. Allied pumped 150 sxs 60/40 pozmix - 10% gel with 300# hulls.
Pulled tubing to 1780'. Allied pumped 150 sxs cement with 200# hulls.
Pulled to 900'. Allied pumped 35 sxs cement - circulated cement.
PTOH. Topped casing off with 5 sxs cement.
Hooked up to backside and pumped 50 sxs cement.
Max. P.S.I. 100#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3816	3993		

INVOICED

DATE 6-7-07
INV. NO. 2007061865

RECEIVED
JUN 04 2007
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams
(TECHNICIAN)

MAY 31 2007

PKG

6-10-25 W
NE SW SW

#1 NC GUIRE

JOHN G. FARMER, INC.

BOX 352, RUSSELL, KS.
CONTR. CO. TOOLS

CITY SPARK

GEOL. SAM. FARMER FIELD NO. 11 E OF SUPPLY ROAD SUR. BY DRY HOLES

E 2531 K.B. c41/29/75 ISSUED 1/29/76 IP P 70 80300 + 6% W LANS 3966-3993 O.A.

API 15-065-20.790

LOG	TOPS	DEPTH	DATUM
A.H.		2149	+ 382
HEER		3747	-1216
TOR		3771	-1240
LANS		3788	-1257
BKC		4018	-1487
LTD		4039	-1508
RID		4040	-1509

8 5/8" 201/175SX 5" 4031/175SX
 DST (1) 3778-3802/30-30-15, REC 90' 5",
 SIP 794#, NO FSIP, FP 95-117#
 DST (2) 3810-44/30-30-45-60, REC 60' 6",
 2040' G&MCO 25% W, 390' W, SIP 572-
 993# FP 202-878#
 DST (3) 3848-69/30-30-60-45, REC 60' 6",
 240' G&MCO, SIP 569-669#, FP 10-32#
 DST (4) 3907-30/30-30, REC 15' M, W/SHOW
 OF 0' SIP 941#, NO FSIP, FP 0#
 DST (5) 3936-80/30-30-60-45, 345' G,
 15' SOCM, 60' G&MCO, 975' GSY MO, 37',
 SIP 1328-1328#, FP 42-416#
 DST (6) 3976-4002/15-30, REC 5' M, W/
 SHOW OF OIL SIP 10#, NO FP
 MICT - PF 24/3987-93, 12/3966-70, AC
 1500 SWB BK 70 BBLs, W/SHOW OIL, SWB
 (800 + 03), 25 BOPH, R&T, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS