

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-30010-00-00
Spot: SESWSE Sec/Twnshp/Rge: 8-14S-2W
306 feet from S Section Line, 1821 feet from E Section Line
Lease Name: DIETER Well #: 2
County: SALINE Total Vertical Depth: 3201 feet

Operator License No.: 6306
Op Name: BROWN, TOM CONSTRUCTION, INC.
Address: 24506 BONNET RD.
ASTOR, FL 32102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3197		50 SX CMT
SURF	8.625	207		150 SX CMT

\$ 104.03

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/13/2006 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand 50' above perms and cap with 4 sx. Set bridge plug @ 300', dump slurry mix to fill from 300' to surface.

Plugging Proposal Received By: GREG EVES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/13/2006 12:00 AM KCC Agent: GREG EVES

Actual Plugging Report:

Rods parted @ 500'. Attempted to fish the remaining rods, was unsuccessful. Tubing also parted in hole. Bottom plug was never placed due to junk in hole. Casing was cut and pulled from 460'. Bridge was set @ 300' and 5 yds slurry mix was dumped to fill to surface.

Perfs:

INVOICED
DATE 6-7-07
INV. NO. 2007061871

~~**INVOICED**
DATE 2/20/02 *PKT*
INV. NO. 2002061398~~

Remarks: SMOKEY VALLEY CONCRETE -TICKET# 015871 TOTAL SLURRY MIX 5YDS SLURRY MIX 22 SX PER YD
10% SAND

Plugged through: CSG

District: 02

Signed Greg Eves

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 29 2007

CONSERVATION DIVISION
WICHITA, KS Form CP-2/3

m

PKT