

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23050-00-00
Spot: NESENW Sec/Twnshp/Rge: 7-7S-20W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: LOEFFLER Well #: A-1
County: ROOKS Total Vertical Depth: 3715 feet

Operator License No.: 33306
Op Name: BLAKE EXPLORATION, LLC
Address: 201 S. MAIN PO BOX 150
BOGUE, KS 67625

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3715	0	w/unknown sxs cmt
SURF	8.625	200	0	w/unknown sxs cmt

\$ 120.74

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/31/2007 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: MIKE DAVIGNON Company: BLAKE EXPLORATION, LLC Phone: (785) 216-0062

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
CIBP 3470'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/31/2007 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 155 sxs 60/40 pozmix - 10% gel with 500# hulls.
Max. P.S.I. 400#. S.I.P. 400#.
Hooked up to backside - instant pressure - blew hole in 8 5/8" below head.

Perfs:

Top	Bot	Thru	Comments
3685	3688		
3657	3663		
3605	3635		
3500	3504		

RECEIVED
JUN 04 2007
KCC WICHITA

INVOICED

DATE 6-7-07
INV. NO. 2007061862

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed *Richard Williams*
(TECHNICIAN)

JUN 01 2007

PKT

N-B COMPANY, INC
RUSSELL, KS 67665


7-07 -20W
NE SE NW

#A-1 LOEFFLER

site: 4-3/4 N & 1 E OF NICODEMUS, KS
contr: EMPHASIS OIL OPERATIONS
geol: BILL GOFF

cty: ROOKS
field: LESAGE NW

API 15-163-23050



fr date 07/11/89 spd date 07/14/89 drig comp 07/20/89 card issued 11/22/89 last revised 11/22/89

ELV: 2188 KB SMP
tops.....depth/datum
ANH.....1760 +428
B/ANH.....1793 +395
TOP.....3171 -983
TOR.....3410 -1222
LANS.....3421 -1233
BKC.....3619 -1431
ARB.....3658 -1470
RTD.....3715 -1527

IP status:

OIL, P 30 BO & 65 BWPD, LKC 3610-3688 OA,
CSG: 8-5/8" 200 / 250 SX; 4-1/2" 3715; PORT COLLAR
AT 1721.62/ 450 SX
NO CORES
DST (1) 3419-3454 (LKC), / 30-30-30-30, REC 1350' SLI
MCW ISIP 718# FSIP 696# IFP 202# -442# FFP 500#
-609#
DST (2) 3449-3482 (LKC), / 30-60-30-60, 60' GIP, REC
435' SLI OCM, ISIP NOT RPTD FSIP 1029# IFP 115#
-157# FFP 220# -252#
DST (3) 3567-3620 (LKC), / 15-15-15-15, REC 10' MUD,
PRESSURES NA

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)