

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-01451-00-01
Spot: SESWNW Sec/Twnshp/Rge: 18-34S-15E
2907 feet from S Section Line, 4279 feet from E Section Line
Lease Name: BROWN Well #: 1 F
County: MONTGOMERY Total Vertical Depth: 601 feet

Operator License No.: 33348
Op Name: DEER RUN OIL LEASE, LLC
Address: 2322 CR 1425
CANEY, KS 67333

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
| PROD | 4.5 | 560 | | |
| SURF | 7 | 20 | | |

\$ 35.00

Well Type: EOR UIC Docket No: E25696.10 Date/Time to Plug: 04/03/2007 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORE'S, INC. Phone: (620) 249-2519

Proposed
Plugging
Method:

TO RUN 1" TO TD AND PUMP GEL AND CEMENT FOR BOTTOM AND TOP PLUGS.

Plugging Proposal Received By: RON ROWE Witness Type: NONE
Date/Time Plugging Completed: 04/03/2007 12:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

RAN 1" HYDRIL INSIDE 4.5" CASING TO 575', GELLED HOLE AND PUMPED 10 SACKS CEMENT FOR BOTTOM PLUG. PULLED 1" UP TO 350' AND PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 1" AND TOPPED OFF WELL. USED TOTAL OF 45 SACKS CEMENT AND 1 SACK GEL.

Perfs:

RECEIVED
KCC DISTRICT #3
MAY 30 2007
CHANUTE, KS

RECEIVED
JUN 04 2007
KCC WICHITA

INVOICED
DATE 6-7-07
INV. NO. 2007061863

Remarks: PLUGGED INJECTION WELL THAT FAILED MIT.

Plugged through:

District: 03

Signed

Ron Rowe by DL
(TECHNICIAN)