

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-24992-00-01
Spot: NENESE Sec/Twnshp/Rge: 9-34S-11E
2310 feet from S Section Line, 165 feet from E Section Line
Lease Name: CASEMENT Well #: 1 B
County: CHAUTAUQUA Total Vertical Depth: 1245 feet

Operator License No.: 31124
Op Name: DOTY, TIM
Address: PO BOX 117
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1245		
SURF	7	40		

\$ 40.46

Well Type: EOR UIC Docket No: E25775.2 Date/Time to Plug: 04/05/2007 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORE'S INC. Phone: (620) 249-2519

Proposed Plugging Method: TO RUN 1" TO TD AND PUMP GEL AND CEMENT FOR BOTTOM AND TOP PLUGS.

Plugging Proposal Received By: RON ROWE Witness Type: PARTIAL
Date/Time Plugging Completed: 04/05/2007 12:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

RAN 1" HYDRIL INSIDE 4.5" CASING TO 400' AND HIT AND DRILLED ON SOLID IRON PLUG OF COLLAPSED 4.5" PIPE, COULD NOT GET THRU W/O HUGE EXPENSE. PUMPED CEMENT, CIRCULATING TO SURFACE. PULLED 1" AND RAN BACK IN HOLE OUTSIDE 4.5" TO 180' AND HIT CEMENT. PUMPED/CIRCULATED CEMENT TO SURFACE BETWEEN 7" SURFACE PIPE AND 4.5" PRODUCTION CASING. PULLED 1" OUT AND TOPPED OFF WELL. USED TOTAL OF 75 SACKS CEMENT.

Perfs:

RECEIVED
KCC DISTRICT #3

MAY 30 2007

CHANUTE, KS

BL

RECEIVED
JUN 04 2007
KCC WICHITA

INVOICED
DATE 6-7-07
INV. NO. 2007061864

Remarks: PLUGGED WELL THAT FAILED MIT IN 2001 WITH DIFFERENT OPERATOR.

Plugged through:

District: 03

Signed

Ron Rowe

(TECHNICIAN)

PRY