

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20630-00-02  
Spot: SWNWSW Sec/Twnshp/Rge: 8-10S-25W  
1650 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: MCGUIRE C Well #: 1  
County: GRAHAM Total Vertical Depth: 2057 feet

Operator License No.: 5135  
Op Name: FARMER, JOHN O., INC.  
Address: 370 W WICHITA AVE PO BOX 352  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		1677		
PROD	4.5	2037	0	w/450 sxs cmt
SURF	8.625	276	0	w/180 sxs cmt
T1	2	1677		

\$ 66.85

Well Type: SWD UIC Docket No: D19538.0 Date/Time to Plug: 05/29/2007 2:00 PM  
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.  
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered out 120 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/29/2007 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 120 sxs 60/40 pozmix - 10% gel w/500# hulls.  
Max. P.S.I. 700#. S.I.P. 600#.  
Hooked up to backside - instant pressure.

Perfs:

Top	Bot	Thru	Comments
1720	1780		

RECEIVED  
JUN 04 2007  
KCC WICHITA

INVOICED  
DATE 6-7-07  
INV. NO. 2007061805

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

170

Signed

*Richard Williams*

(TECHNICIAN)

MAY 31 2007

177


JOHN O. FARMER, INC.  
BOX 352

8-10-25W  
#1 MC GUIRE 'OWWO' SW NW SW

RUSSELL, KS 67665  
CONTR JOHN O. FARMER, INC. CTY GRAHAM

GEOL \_\_\_\_\_ FIELD GURK NE

E 2516KB CM 1/6/79 CARD ISSUED 2/17/79 IP SWDW  
1728-80



API 15-065-20-630-A

SMP	TOPS	DEPTH	DATUM
ANH		2127	+389
HEEB		3736	-1220
LANS		3776	-1260
BKC		4007	-1491
RTD		4010	-1494

OLD OPERATOR WAS: OKMAR OIL CO.  
#1 MC GUIRE "C" SPD-11/8/73 COMPLETED  
AS D&A/BKC 10/22/73

8 5/8" 276/180sx  
DST(1) 3744-3790/45-45-45-45, REC  
1400' SO CMSW, SIP 889-924, FP  
213-889#  
DST(2) 3794-3814/45-45-60-60, WEAK BLOW  
REC 80' SO CM, SIP 951-936#, FP 31-  
40#  
DST(3) 3813-3862/45-45-60-60, REC 120'  
SOCMW, SIP 813-764#, FP 70-111#  
NO LOG

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

JOHN O. FARMER, INC. 8-10-25W  
#1 MCGUIRE 'OWWO' SW NW SW

RE-ENTERED 1/6/79, CO TO 2057, SET 4 1/2" 2037/450sx, MICT - CO  
PF 1728-80, SWB, REC GSD, FL 550 FROM TOP, RNG TBG, SWDW,  
INJ RATE SAT.