

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-01137-00-01
Spot: NENENE Sec/Twnshp/Rge: 12-11S-19W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: GLADYS Well #: 7
County: ELLIS Total Vertical Depth: 3660 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3620	0	150 SX
SURF	8.625	180	0	150 SX

\$ 118.95

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/29/2007 5:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 658-7258

Proposed Plugging Method: Ordered 250 sxs SMD and 1000# hulls.
Deep casing leaks - squeezed at 2700' - 2800'.
PF 1405' - squeezed with 275 sxs.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/29/2007 7:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed at 150'.
Express Well Service RIH with tubing to 2138'.
Swift Cementing rigged to tubing and pumped 80 sxs SMD with 400# hulls mixed in.
Pulled tubing to 1450' - rigged to tubing and pumped 60 sxs SMD with 200# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 4 1/2" casing with a swedge and pumped 15 sxs SMD with 100# hulls mixed in.
Max. P.S.I. 400#. S.I.P. 350#.
Cut hole in 8 5/8" casing.
Backside full of cement.

Perfs:

INVOICED
DATE 6-7-07
INV. NO. 2007061867

RECEIVED
JUN 4 2007
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS GASAWAY #M-1. SWIFT CEMENTING COMPANY-TICKET #1493.

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

MAY 31 2007

PKT


D/VI// BROS & TRANSIT CORP #1 GASAWAY PH 12-11-19W
 NE NE NE

Contr. TRANSIT CORP ELLIS County

E 2053RB Comm. Comp. 1-8-60 IP D & A

Tops	Depth	Datum
ANH	1395	+658
TOP	3046	-993
HEEB	3269	-1216
TOR	3284	-1231
LANS	3308	-1255
B/KC	3533	-1480
CONG	3558	-1505
SIMP DOL	3611	-1558
ARB	3634	-1581
TD	3660	-1607

Casing
 8" 180
 DST 3274-3375/1 HR, 60° M, BHP 560#
 DST 3374-3435/2 HR, 90° M, BHP
 1130#
 DST 3452-3548/1 HR, 40° M, BHP 755#
 DST 3531-3621/1 HR, 35° M, BHP
 310#



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS