

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21933-00-00
Spot: N2SWNW Sec/Twnshp/Rge: 12-11S-19W
3630 feet from S Section Line, 4620 feet from E Section Line
Lease Name: GLADYS Well #: 5
County: ELLIS Total Vertical Depth: 3700 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3695	0	150 SX CMT
SURF	8.625	170	0	135 SX CMT

\$ 120.25

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/29/2007 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 658-7258

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 10% gel - 1600# hulls - 15 sxs SMD cement.
Casing leaks.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/29/2007 4:40 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed at 2025' - 1450' - 750' - 150'.
Express Well Service RIH with tubing to 2138'.
Swift rigged to tubing and pumped 230 sxs 60/40 pozmix with 600# hulls mixed in.
Pulled tubing to 1400' - rigged to tubing and pumped 110 sxs with 500# hulls mixed in.
Pulled tubing to 1000' - rigged to tubing and pumped 110 sxs with 500# hulls mixed in.
Pulled tubing to 750' and pumped 5 sxs SMD to circulate cement to surface out of 4 1/2" casing.
Pulled tubing - rigged to 4 1/2" casing with a swedge and pumped 5 sxs SMD.
Max. P.S.I. 400#. S.I.P. 375#.
Cut hole in 8 5/8" - topped off with 5 sxs SMD.
Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3666	3670		
3655	3657		
3332	3493		

RECEIVED
JUN 04 2007
KCC WICHITA

INVOICED

Remarks: SWIFT CEMENTING SERVICES-TICKET #1492.

DATE 6-7-07
INV. NO. 2007061867

Plugged through: TBG

District: 04

Signed _____
(TECHNICIAN)

MAY 31 2007

PKT

