

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-02323-00-00
Spot: NWSESW Sec/Twnshp/Rge: 12-26S-18E
849 feet from S Section Line, 3627 feet from E Section Line
Lease Name: RATH Well #: 9
County: ALLEN Total Vertical Depth: 850 feet

Operator License No.: 5488
Op Name: TWM PRODUCTION CO., A GENERAL P
Address: 1150 HWY 39
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	850		
SURF	10	20		

\$ 35.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/05/2007 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MICHAEL J. WIMSETT Company: W & W PRODUCTION COMPANY, Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850" THAT HAD BEEN CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/05/2007 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 200'. AT THAT DEPTH PROGRESS WAS STOPPED. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. 1" PIPE WAS RAN INTO 2" AND 10" ANNULUS TO 175'. AT THAT DEPTH CEMENT WAS ENCOUNTERED. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 10" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED AND DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

INVOICED
DATE 6-7-07
INV. NO. 2007061868

RECEIVED
KCC DISTRICT #3

MAY 31 2007

CHANUTE, KS

RECEIVED
JUN 04 2007
KCC WICHITA

Remarks: SPOT LOCATION ESTABLISHED BY GPS AS RAT09

Plugged through:

District: 03

Signed Clayton P Titel by BL
(TECHNICIAN)