

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20069-00-00
Spot: NE Sec/Twnshp/Rge: 28-18S-31W
3958 feet from S Section Line, 1372 feet from E Section Line
Lease Name: MILDRED STRODE Well #: 1
County: SCOTT Total Vertical Depth: 2810 feet

Operator License No.: 32356
Op Name: INTERMOUNTAIN REFINING CO, INC
Address: PO BOX 35
FARMINGTON, NM 87499

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	<u>04.50</u>	2808		WITH 150 SX CMT
SURF	8.625	220		WITH 125 SX CMT

\$ 91.33

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/21/2007 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: WAYNE WILSON Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2007 6:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TOC FROM BOND LOG IS 920'. 1ST PLUG TIH WITH TUBING TO 2380' & PUMP 25 SX CMT. 2ND PLUG TRIP IN HOLE WITH TUBING TO 2030' & PUMP 80 SX CMT. TOC @ 600'. PERFORATE CASING AT 540' WITH 4 SHOTS. 3RD PLUG TIH WITH TUBING TO 495'. SET PACKER @ 495' AND CIRCULATE CMT FROM 540' TO SURFACE WITH 150 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2756	2762		
2745	2747		

INVOICED
DATE 6-12-07
INV. NO. 2007061890

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01



Signed

[Signature]

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 06 2007

CONSERVATION DIVISION
WICHITA, KS