

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: ^{02 KCCap} ~~15-079-20587-00-07~~ ^{6-21-07.}
Spot: E2W2NW Sec/Twnshp/Rge: 18-23S-3W
3960 feet from S Section Line, 4290 feet from E Section Line
Lease Name: PIZINGER Well #: 3
County: HARVEY Total Vertical Depth: 3425 feet

Operator License No.: 5091
Op Name: HOWELL OIL COMPANY, INC.
Address: 9 LOIS LANE
BELLA VISTA, AR 72715

PROD Size: 5.5 feet: 3424 125 SX CMT'
SURF Size: 10.75 feet: 289
³¹
#111

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/03/2004 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY JOE Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand to 3310' and 5 sxs; 550' & 35 sxs; 350' to 0'.

RECEIVED
KCC DISTRICT #9
FEB 12 2004
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2004 5:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 3310' and 5 sacks of cement. Shot 5-1/2" casing off at 1028'. Pulled to 550'. Pumped 35 sacks of cement with 100 lbs of cotton hulls and 3% cc. Pulled to 350'. Circulate cement to surface.
Cement fell. Used 11 sacks of cement to bring it back to surface.
60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3360	3366		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 24 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENTING #24085

Plugged through: CSG

District: 02

Signed

Jack Luthi

(TECHNICIAN)

INVOICED

DATE 2.24.04

INV. NO. 200406/216