

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03268-00-00

Spot: SENENE

Sec/Twnshp/Rge: 6-16S-12W

4290 feet from S Section Line,

330 feet from E Section Line

Lease Name: N W BEAVER UNIT

Well #: T4-W1

County: BARTON

Total Vertical Depth: 3343 feet

Operator License No.: 5363

Op Name: BEREXCO, INC.

Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3200	0	w/100 sxs cmt
SURF	8.625	526	0	w/245 sxs cmt <u>\$108.65</u>

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/30/2007 2:00 PM

Plug Co. License No.: 5363

Plug Co. Name: BEREXCO, INC.

Proposal Rcvd. from: BOB GRANT

Company: BEREXCO, INC.

Phone: (316) 265-3311

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 04/30/2007 6:15 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Perforated at 1590' -750' -575'.
Ran tubing to 3016' - pumped 100 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
Pulled to 1600' - pumped 120 sxs cement with 200# hulls - cement circulated.
POOH. Pumped 70 sxs cement with 100# hulls down casing - cement circulated up 8 5/8" annulus.
Shut in annulus. Pumped 10 sxs down casing.
Max. P.S.I. 500#. S.I.P. 200#.

INVOICED
DATE 6-20-07
INV. NO. 2007061918

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 15 2007

CONSERVATION DIVISION
WICHITA, KS

Remarks: LEASE ORIGINALLY KNOWN AS STANDINGER D-1. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

CASE MORRIS

(TECHNICIAN)

Form CP-2/3

MAY 29 2007

PHIL HAN OIL COMPANY #1 STANDINGER D 6-16-12
SE NE NE ✓

Contr. _____ BARTON _____ County

E 1848 Comm. _____ Comp. 3-26-48 IP 100 BOPD

Tops	Depth	Datum
ANH	788	+1060
TOP	2678	830
HEELB	2932	1084
LANS	3028	1180
T.D.	3308	1760

Casing

8" 526 PERF 27 S, 3107-12
5" 3308 PERF 55 S, 3056-67
ACID 500
SWB 4 EOPH/8 HRS:

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

