

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-19004-004202 <sup>kc</sup> ap 6-2507  
Spot: W2NESE , Sec/Twnshp/Rge: 31-8S-24W  
1980 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: HOLLEY UNIT Well Number: 8-8  
County: GRAHAM Total Vertical Depth: 1935 feet

Operator License No.: 30420  
Op Name: INNONE, VINCENT D/B/A V.J.I. NATUR  
Address: 30-38 48TH STREET  
ASTORIA, NY 11103

Production Casing Size: 7 feet: 1934 250 SX CMT  
Surface Casing Size: 10.75 feet: 110 100 SX CMT

\$62<sup>89</sup>

Well Type: WSW UIC Docket No: Date/Time to Plug: 10/23/2003 2:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JASON DINGES Company: V.J.I. NATURAL RESOURCES Phone: (785) 625-8360

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 10% gel - 500# hulls.  
WSW Perfs: 1720' - 1900'.  
Fluid level 200'. PBTB 1900'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/23/2003 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Swift Services hooked up to 7" casing.  
Injection rate 4 bpm 250#.  
Swift Services pumped 275 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Max. P.S.I. 450#. S.I.P. 175#.

12-13-2003 - Backside verified cement at surface.

RECEIVED  
DEC 19 2003  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

12-22-03

BY, NO.

2004060973

OCT 27 2003