

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

19013-00-01

API Well Number: 15-127-20464-00-01
Spot: NWNWNW Sec/Twnshp/Rge: 35-15S-9E
4943 feet from S Section Line, 4958 feet from E Section Line
Lease Name: OLSEN ~~OWW~~ WD Well #: 1
County: MORRIS Total Vertical Depth: 3176 feet

Operator License No.: 6142
Op Name: TOWN OIL COMPANY INC.
Address: 16205 W. 287 ST.
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	2986		253 SX CMT OF 1st COMPLETION
PROD	5.5	3159		175 SX CMT OF 2nd COMPLETION
SURF	8.625	151		75 SX CMT

#103²²

Well Type: SWD UIC Docket No: D23568.0 Date/Time to Plug: 12/16/2005 10:00 AM
Plug Co. License No.: 6142 Plug Co. Name: TOWN OIL COMPANY INC.
Proposal Rcvd. from: LESTER TOWN Company: TOWN OIL COMPANY INC. Phone: (913) 285-1278

Proposed Plugging Method: Run tubing inside of 2-7/8" production tubing. Pump cement to fill tubing to surface from 1000'. Ensure that tubing, production casing, and surface casing annulus are all cemented to surface.

Plugging Proposal Received By: GREG EVES WitnessType: NONE
Date/Time Plugging Completed: 12/16/2005 1:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Ran 1" tubing to 1050' and pumped cement to fill 2-7/8" from 1050' to surface. Pulled 1" tubing and topped off cement to surface. This was a fluid depression well, so the tubing and casing were already cemented in.

60/40 posmix with 4% gel

Consolidated Well Service #5027

Perfs:

RECEIVED
KCC DISTRICT #2
DEC 23 2005
WICHITA, KS

RECEIVED
JAN 03 2006
KCC WICHITA

Remarks: PLUGGED THROUGH 1" TUBING AKA/ OLSEN #5

Plugged through: TBG

District: 02

INVOICED

Signed

Greg Eves

(TECHNICIAN)

DATE

1-3-06

INV. NO.

2006060937