

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-071-20830-00-00  
Spot: SENWNWSE Sec/Twnshp/Rge: 9-17S-40W  
2145 feet from S Section Line, 2145 feet from E Section Line  
Lease Name: KERO Well #: 1  
County: GREELEY Total Vertical Depth: 3050 feet

Operator License No.: 32920  
Op Name: W. R. WILLIAMS, INC.  
Address: PO BOX 15163  
AMARILLO, TX 79105

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3049	0	WITH 600 SX CMT
SURF	8.625	299		WITH 175 SX CMT

**\$ 99.13**

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/23/2007 11:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DAVE OLSEN Company: W.R. WILLIAMS Phone: (806) 374-4555

Proposed Plugging Method: PUMP 400# HULLS & 250 SX CMT. EXTRA 100 SX CMT FOR ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/23/2007 1:30 PM KCC Agent: KEN JEHLIK

**Actual Plugging Report:**

FILLED 4 1/2" CASING WITH 400# HULLS & 175 SX CMT. PRESSURE TO 600# & HELD. PUMP 8 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS. PRESSURED TO 500# & HELD.

**Perfs:**


Top	Bot	Thru	Comments
2992	2998		
2982	2988		
2966	2976		

**INVOICED**  
DATE 6-13-07  
INV. NO. 2007061901

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed *Ken Jehlik*  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 11 2007

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

*[Handwritten signature]*