

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: EOG Resources, Inc.

Address: 3817 NW Expressway, Suite 500 Oklahoma City, OK 73112-1483

Phone: (405) 246-3100 Operator License #: 5278

Type of Well: DH KCCPKT PercP2/3 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 5/31/2007 (Date)

by: Lynn Reimer (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Basal Chester Depth to Top: 5804' Bottom: 5810' T.D. 5900'

Chester Depth to Top: 5560' Bottom: 5582' T.D.

Depth to Top: Bottom: T.D.

API Number: 15 - 025-21372 -00-00

Lease Name: Dunne Ranch 31

Well Number: 31 #1 KCCPKT PercP2/3

Spot Location (QQQQ): C NE NW SESW

1980 Feet from North / South Section Line

1980 Feet from East / West Section Line

Sec. 31 Twp. 34 S. R. 23 East West

County: Clark

Date Well Completed: 10/17/2006

Plugging Commenced: 6/4/2007

Plugging Completed: 6/6/2007

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Pump 85 bbls mud down casing & set 4 1/2" CIBP @ 5510', cap w/ 2 sks cement. Cut & pull 4 1/2" csg from 2968'. Run tbg @ 892' mix & pump 100 sks class "C" cement @ 14.8 ppg w/ 1.32 yield up to 550'. Pull up hole w/ tbg @ 314', mix & pump 40 sks class "C" cement up to 214' to cover 13 3/8" shoe. Top out 34' - 4' w/ 10 sks cement. 13 3/8" X 8 5/8" annulus full to surface.

Name of Plugging Contractor: Orr Enterprises, Inc. License #: 33338

Address: P.O. Box 1706 Duncan, OK 73534

Name of Party Responsible for Plugging Fees: EOG Resources Inc. JUN 22 2007

State of OK County, Oklahoma, ss.

Bev Christensen (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

NOTARY SEAL PUBLIC HEATHER NEALSON Cleveland County Notary Public in and for State of Oklahoma Commission # 04003796 Expires 4/26/08

(Signature) Bev Christensen (Address) 3817 NW Exp. Ste 500, Oklahoma City OK 73112-1483 SUBSCRIBED and SWORN TO before me this 20th day of JUNE, 2007 My Commission Expires: 4-26-08