

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Sunfire Energy
Address: PO Box 1761 Liberal KS 67905
Phone: (620) 624-7031 Operator License #: 32126
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5-15-07 (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 5926 Bottom: 5956 T.D. 6030
St Louis Depth to Top: 5886 Bottom: 5899 T.D. _____
Chester Depth to Top: 5614 Bottom: 5626 T.D. _____

API Number: 15-175-20677-0001
Lease Name: Kulp
Well Number: 1-33
Spot Location (QQQQ): C-NE-NE-SW
2310 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 33 Twp. 32 S. R. 31 East West
County: Seward
Date Well Completed: 1-18-83 ^{original} 9/19/05 ^{KCC}
Plugging Commenced: 5-15-07 ^{PPT}
Plugging Completed: 5-17-07 ^{7/3/07} ^{PER RB5}

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				13 3/8	530	-
				8 5/8	1608	-
				4 1/2	6030	2509


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 200 lb. hulls + 20 sx cmt. to plug perfs from 5614 to 5414. Shot + pull 4 1/2 to 1630. Circ. hole w/mud + mixed 50 sx 1630 to 1480 40 sx 540 to 420 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: RT. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Sunfire Energy
State of Kansas County, Seward, ss.
Gerald M. Roberts (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gerald M. Roberts

(Address) P.O. Box 1761 Liberal, KS 67905



My Appt. Expires 8-14-2010 SUBSCRIBED and SWORN TO before me this 21 day of June, 2007
Tawana Earnest My Commission Expires: 8/14/2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

JUN 27 2007

CONSERVATION DIVISION