

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: W. D. Short Oil Co., LLC

Address: P. O. Box 729-102 S. River Rd., Oxford, Ks. 67119

Phone: (620) 455 - 3576 Operator License #: 33608

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10-21-2005 (Date)

by: David Williams (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Mississippi Depth to Top: 3097 Bottom: 3118 T.D. 3118

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 035-02123 - 00 - 00

Lease Name: Hart

Well Number: 2

Spot Location (QQQQ): C - SE - NE - SE

1650 Feet from ☐ North / ☒ South Section Line

330 Feet from ☒ East / ☐ West Section Line

Sec. 2 Twp. 34 S. R. 5 ☒ East ☐ West

County: Cowley

Date Well Completed: 04-03-1957

Plugging Commenced: 04/17/2007

Plugging Completed: 05/22/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi	Oil	3097	3118	8-5/8"	97'	0
				4-1/2"	3099'	840'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded Back to 3015', Dumped 4 sx. cement w/ dump bailer on top of sand, Shot pipe off @ 840', Pulled and laid down
Pipe, Loaded Hole w/ 40 Bbl. of Fresh Water, Ran 1" Pipe to 250' and Pumped 100 sx. of Cement, topped of with cement, Rigged down and
cleaned up location.

Name of Plugging Contractor: Braden Petroleum & Well Plugging License #: 32475

Address: P.O. Box 282, Burden, Ks. 67019

Name of Party Responsible for Plugging Fees: W. D. Short Oil Co., LLC


State of Kansas County, Sumner, ss.

William D. (Don) Short, Jr.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) William D. Short Jr.

(Address) P.O. Box 729, 102 S. River Rd. Oxford, Ks. 67119



SUBSCRIBED and SWORN TO before me this 25th day of June, 2007

Notary Public

My Commission Expires: 3-30-09 RECEIVED

KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

JUN 26 2007

CONSERVATION DIVISION
WICHITA, KS

BRADEN PETROLEUM & WELL PLUGGING

10139 SW HAVERHILL RD
AUGUSTA, KS 67010

FILE COPY

JAMES R. BRADEN

HOME # 316-775-6435 MOBILE # 620-222-1252

DATE

6-18-07
5/30/2007

INVOICE #

07/569

BILL TO

SHORT COMPANIES
P.O. BOX 729
OXFORD, KS. 67119

JOB LOCATION

HART #2

TERMS 30 DAYS

Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
4/17/2007		MOVED IN ON LOCATION. RIGGED UP TO PLUG BOTTOM. SANDED BACK TO 3015, DUMPED 4 SX. CEMENT ON TOP OF SAND WITH DUMP BAILER. DUG OUT CELLAR.	
4/16/2007		RIGGED UP JACKS. PULLED SLIPS, WORKED PIPE. PIPE PULLED INTO @ 145', LAYED OUT BAD PIN. REPLACED BOTTOM JOINT, RUN BACK IN SCREWED ON. SHOT WOULDN'T GO PASSED 860', FOUND COLLAR @ 840'. SHOT OFF, LAYED OUT 4 1/2" PIPE. LOADED JACKS, RIGGED DOWN.	
	RIG UP CHARGE		1,200.00T
	PIPE PULLING CHARGE	1000' MINIMUM @ \$0.65 PER FT.	650.00T
	SHOOTING CHARGE	1 SHOT @ \$350.00 PER SHOT	350.00T

Thank you for your business.

SUBTOTAL \$2,200.00

SALES TAX (5.8%) \$127.60

BALANCE DUE \$2,327.60

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 26 2007

CONSERVATION DIVISION
WICHITA, KS

BRADEN PETROLEUM & WELL PLUGGING

10139 SW HAVERHILL RD
AUGUSTA, KS 67010

FILED
STANDARD

6-18-07 DAYS

JAMES R. BRADEN
HOME # 316-775-6435 MOBILE # 620-222-1252

DATE	INVOICE #
5/30/2007	07/572

BILL TO
SHORT COMPANIES P.O. BOX 729 OXFORD, KS. 67119

JOB LOCATION
HART #2

TERMS 30 DAYS
Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
5/22/2007		MOVED IN ON LOCATION. LOADED WATER TANK WITH 40 BBL. FRESH WATER. RIGGED UP TO PUMP CEMENT. RUN 1" DOWN INSIDE 85/8" SURFACE PIPE TO 250'. PUMPED 100 SX. CEMENT FILLED TO THE TOP. PULLED OUT 1", TOPPED OF WITH CEMENT. WASHED UP, RIGGED DOWN.	
	CEMENT	100 SACKS- 4% GEL @ \$7.65 PER SACK	765.00T
	PUMP CHARGE	3 HRS @ \$100.00 PER HR.	300.00T
	BULK TANK	\$100.00 PER JOB	100.00T
	WATER TRUCK	3 HRS. @ \$50.00 PER HR.	150.00T

Thank you for your business.

SUBTOTAL	\$1,315.00
SALES TAX (5.8%)	\$76.27
BALANCE DUE	\$1,391.27

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 26 2007

CONSERVATION DIVISION
WICHITA, KS