

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: W. D. Short Oil Co., LLC
Address: P. O. Box 729-102 S. River Rd., Oxford, Ks. 67119
Phone: (620) 455-3576 Operator License #: 33608
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: Nov. 27, 2006 (Date)
by: Barry Metz (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 3065 Bottom: 3096 T.D. 3096

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-035-02108-00-00
Lease Name: Brown
Well Number: 3
Spot Location (QQQQ): S0 N0 W5 E0
W/2 W/2 SW
1320 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 2 Twp. 34 S. R. 5 East West
County: Cowley
Date Well Completed: 11-29-1956
Plugging Commenced: 04/06/2007
Plugging Completed: 05/22/2007

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi	Oil	3065	3096	8-5/8"	95'	0
				5-1/2"	3065'	825'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded back to 3015', Dumped 6 sx. Cement on Top of Sand w/ Dump Bailer, Shot off pipe @ 825', Laid Down Pipe, Loaded Hole w/ 40 BBI.
Fresh water, Ran 1" to 240', pumped 95 sx. cement, Rig down and clean up location.

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 26 2007

Name of Plugging Contractor: Braden Petroleum & Well Plugging License #: 32475
Address: P.O. Box 282, Burden, Ks. 67019
Name of Party Responsible for Plugging Fees: W. D. Short Oil Co., LLC
State of Kansas County, Sumner, ss.

CONSERVATION DIVISION
WICHITA, KS

William D. (Don) Short, Jr. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P.O. Box 729, 102 S. River Rd. Oxford, Ks. 67119

SUBSCRIBED and SWORN TO before me this 25th day of June, 2007
DENESE A. WILSON
Notary Public - State of Kansas
My Appt. Expires 3-30-09
My Commission Expires: 3-30-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]

BRADEN PETROLEUM & WELL PLUGGING

10139 SW HAVERHILL RD
AUGUSTA, KS 67010

JAMES R. BRADEN
HOME # 316-775-6435 MOBILE # 620-222-1252

DATE	INVOICE #
5/30/2007	07/568

BILL TO
SHORT COMPANIES
P.O. BOX 729
OXFORD, KS. 67119

JOB LOCATION
BROWN #3

TERMS 30 DAYS
Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
4/6/2007		MOVED IN ON LOCATION. RIGGED UP TO PLUG BOTTOM. SANDED BACK TO 3015, DUMPED 6 SX. CEMENT ON TOP OF SAND WITH DUMP BAILER. DUG OUT CELLAR.	
4/16/2007		RIGGED UP JACKS. PULLED SLIPS, WORKED PIPE. SHOT OFF @ 825' LAYED OUT 5 1/2" PIPE. LOADED JACKS, RIGGED DOWN.	
	RIG UP CHARGE		1,200.00T
	PIPE PULLING CHARGE	1000' MINIMUM @ \$0.65 PER FT.	650.00T
	SHOOTING CHARGE	1 SHOT @ \$350.00 PER SHOT	350.00T

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 26 2007
CONSERVATION DIVISION
WICHITA, KS

Thank you for your business.	SUBTOTAL	\$2,200.00
	SALES TAX (5.8%)	\$127.60
	BALANCE DUE	\$2,327.60

BRADEN PETROLEUM & WELL PLUGGING

10139 SW HAVERHILL RD
AUGUSTA, KS 67010

JAMES R. BRADEN
HOME # 316-775-6435 MOBILE # 620-222-1252

DATE	INVOICE #
5/30/2007	07/571

BILL TO
SHORT COMPANIES P.O. BOX 729 OXFORD, KS. 67119

JOB LOCATION
BROWN #3

TERMS 30 DAYS
Charge of 1.8% on due accounts

DATE	ITEM	DESCRIPTION	AMOUNT
5/22/2007		MOVED IN ON LOCATION. LOADED WATER TANK WITH 40 BBL. FRESH WATER. RIGGED UP TO PUMP CEMENT. RUN 1" DOWN INSIDE 85/8" SURFACE PIPE TO 240'. PUMPED 95 SX. CEMENT FILLED TO THE TOP. PULLED OUT 1", TOPPED OF WITH CEMENT. WASHED UP, RIGGED DOWN.	
	CEMENT	95 SACKS- 4% GEL @ \$7.65 PER SACK	726.75T
	PUMP CHARGE	3 HRS @ \$100.00 PER HR.	300.00T
	BULK TANK	\$100.00 PER JOB	100.00T
	WATER TRUCK	3 HRS. @ \$50.00 PER HR.	150.00T

Thank you for your business.	SUBTOTAL	\$1,276.75
	SALES TAX (5.8%)	\$74.05
	BALANCE DUE	\$1,350.80

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 26 2007

CONSERVATION DIVISION
WICHITA, KS