

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-24247-00-00  
Spot: N2SWNE Sec/Twnshp/Rge: 5-12S-20W  
3630 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: SCHMEIDLER Well #: 2  
County: ELLIS Total Vertical Depth: 3964 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3959	0	w/175 sxs cmt
SURF	8.625	256	0	w/160 sxs cmt

\$ 128.83

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/25/2007 1:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM, INC. Phone: (316) 524-1225

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
1285' top of junk in the hole  
No fluids.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/26/2007 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

06/25/2007 - Copeland rigged to 4 1/2" casing and pumped 2.5 BBLs water - well locked up at 700#.  
Operator will get pulling rig to run tubing.  
06/26/2007 - DS&W RIH with tubing to 1240'. Copeland rigged to tubing - pumped 70 sxs to circulate cement out of 4 1/2" casing.  
Pulled tubing - rigged to 4 1/2" casing with a swedge - pumped 10 sxs cement.  
Max. P.S.I. 300#. S.I.P. 300#.  
Rigged to 8 5/8" casing - pumped 15 sxs cement with 200# P.S.I.  
Blew small hole in casing at the top.  
S.I.P. 0#.

Perfs:

Top	Bot	Thru	Comments
3887	3897		

**INVOICED**  
DATE 7-6-07  
INV. NO. 2008060039

Remarks: COPELAND ACID & CEMENTING-TICKET #32486.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

JUL 02 2007

CONSERVATION DIVISION  
WICHITA, KS

JUN 28 2007

replacement card

ROCKHOUND RESOURCES  
GREAT BEND KS

5-12S-20W  
C N/2 SW NE

# 2 SCHMEIDLER

site: 6-1/2 N OF ELLIS KS  
contr: DUKE DRILLING  
geol: ROD TREMBLAY

city: ELLIS  
field: NICHOLSON SE

API 15-051-24247

fr date 05/30/85    spd date 05/30/85    drig comp 06/04/85    card issued 09/26/85    last revised 06/09/97


ELV: 2286 KB, 2281 GL LOG

tops.....	depth/datum
ANH.....	1699 + 587
TOP.....	3335 - 1049
HEEB.....	3559 - 1273
TOR.....	3583 - 1297
LANS.....	3598 - 1312
BKC.....	3838 - 1552
MARM.....	3886 - 1600
ARB.....	3928 - 1642
RTD.....	3960 - 1674
LTD.....	3964 - 1678

**IP status:**  
**OIL, P 35 BO & 35 BWPD, MARM 3887-3897, 06/20/85**  
 CORR & INFO REL: 6/9/97 - CORR DATES; WAS TEMP  
 COMP  
 CSG: 8-5/8" 256 / 160 SX, 4-1/2" 3959 / 175 SX, DV TOOL  
 AT 1769 / 450 SX  
 DST (1) 3554-3603 (TOR, LANS), / 30-30-30-30, WB &  
 BLDG ON BOTH OPENS, 90' GIP, REC 95' HVY OILY  
 GCM ISIP 976# FSIP 936# IFP 39# -49# FFP 49# -61#  
 IHP 1686# FHP 1669#  
 DST (2) 3833-3910 (MARM), / 30-45-30-45, WB ON BOTH  
 OPENS, REC 35' HVY OILY GCM ISIP 640# FSIP 630#  
 IFP 29# -49# FFP 49# -61# IHP 1906# FHP 1891#

COPYRIGHT 1997  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)