

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-141-20365-00-00
Spot: SESWNE Sec/Twnshp/Rge: 29-8S-13W
2310 feet from N Section Line, 1650 feet from E Section Line
Lease Name: SARVER TRUST Well #: 1-29
County: OSBORNE Total Vertical Depth: 3028 feet

Operator License No.: 33599
Op Name: REE, BILL DBA BARLINE OIL COMPA
Address: 2103 DALTON
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3027	0	75 SX
SURF	8.625	207	0	158 SX

\$ 98.41

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/08/2007 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BUTCH JACKSON Company: BARLINE OIL COMPANY Phone: (620) 786-7057

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 10% gel and 400# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/08/2007 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Cut casing off at 2300'.
Pulled casing to 1150' - pumped 75 sxs cement with 300# hulls.
Pulled casing to 725' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 200' - pumped 35 sxs cement - circulated to surface.
Topped off if needed.

Perfs:

Top	Bot	Thru	Comments
3019	3025		
2754	2758		

INVOICED

DATE 7-6-07
INV. NO. 2008060038

Remarks: COPELAND ACID & CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Pat Bedore PRTI

(TECHNICIAN RECEIVED)
KANSAS CORPORATION COMMISSION

JUN 25 2007

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

JUN 15 2007