

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21009-00-00
Spot: N2NWNW Sec/Twnshp/Rge: 22-15S-13W
4950 feet from S Section Line, 4620 feet from E Section Line
Lease Name: ESFELD Well #: 5
County: RUSSELL Total Vertical Depth: 3341 feet

Operator License No.: 32826
Op Name: MICHAELIS, ROGER DBA ALEO OIL CO
Address: 1864 NW 20 AVE.
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3339	0	w/unknown sxs cmt
SURF	8.625	250	0	w/unknown sxs cmt

\$ 108.58

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/04/2007 9:00 AM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVID FUNK Company: ALEO OIL COMPANY Phone: (785) 324-1041

Proposed
Plugging
Method:

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/04/2007 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfed at 1550' - 870' - 475'.
Ran tubing to 3000' - pumped 100 sxs 60/40 pozmix - 10% gel cement with 600# hulls.
Pulled to 1800' - pumped 130 sxs cement with 100# hulls - cement circulated.
POOH. Tied onto 5 1/2" - pumped 60 sxs cement.
Max. P.S.I. 700#. S.I.P. 300#.
Backside did not circulate.
06/05/2007 - Cut off head - welded plate on top - pumped 25 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.

Perfs:

Top	Bot	Thru	Comments
3326	3328		
3320	3322		
3235	3238		
3215	3219		
3085	3089		
2993	2997		

INVOICED

DATE 7-6-07
INV. NO. 2008060035

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 04

110

Signed Case Morris
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION CP-2/3

JUN 28 2007

CONSERVATION DIVISION
WICHITA, KS

JUN 18 2007

Handwritten initials

W.E.D., INC.
DRAWER 546, WILSON, KS.

#5 ESFELD

22-15-13W
N/2 NW NW

CONTR REVLIN DRLG. CTY RUSSELL

GEOL RICHARD SCHMIDT FIELD TRAPP

E 1890 KB CM 3/18/77 CARD ISSUED 6/16/77 IP P 25 BOPD, NW
ARB 3320-22

+	+
+	+

API 15-167-21,009

LOG	TOPS	DEPTH	DATUM
TOP		2744	- 854
HEEB		2973	-1083
TOR		2997	-1107
LANS		3051	-1161
BKC		3244	-1354
ARB		3316	-1426
RTD		3341	-1451

8-5/8" 250, ⁵/₂" 3339
NO DST'S
MICT - CO, PF (ARB) 8/3320-22, SWB 12
BOPH, NW, NAT, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS