

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-23123-00-00  
Spot: W2W2SE Sec/Twnshp/Rge: 34-17S-13W  
1320 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: DOVE Well #: 3-34  
County: BARTON Total Vertical Depth: 3430 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3425	0	150 SX
SURF	8.625	325	0	200 SX

\$ 111.48

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/28/2007 10:00 AM  
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.  
Proposal Rcvd. from: KEVIN WILES Company: AMERICAN WARRIOR, INC. Phone: (620) 272-4996

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Emergency plug with rig over the hole.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/28/2007 2:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech RIH and perfed at 1450' - 785' - 375'.  
Chase Well Service RIH with tubing to 2206'. Allied rigged to tubing - pumped 80 sxs 60/40 pozmix with 300# hulls mixed in.  
Pulled tubing to 1458'. Allied rigged to tubing - pumped 200 sxs cement with 200# hulls mixed in to circulate cement up 5 1/2".  
Pulled tubing - rigged to 5 1/2" casing - pumped 20 sxs to circulate cement out of 8 5/8".  
Shut in 8 5/8" - pumped 25 sxs cement.  
Max. P.S.I. 200#. S.I.P. 125#.

Perfs:

Top	Bot	Thru	Comments
3356	3370		

**INVOICED**  
DATE 7-6-07  
INV. NO. 2008060036

Remarks: ALLIED CEMENTING COMPANY-TICKET #30570.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 02 2007 Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

JUN 28 2007

ALLEN DRILLING COMPANY

P.O. BOX 1389

#3-34 DOVE

34-17-13W

C W/2 W/2 SE


GREAT BEND, KS 67530

CONTR COMPANY TOOLS

CTY BARTON

GEOLOGICAL RANDY LILAK

FIELD MCCAULEY



ELV 1875 KB SPD 5/24/83 CARD ISSUED 6/23/83 IP P 50 BOPD, NW

1870 GL

ARB 3368-3370

API 15-009-23,123

LOG	Tops	Depth-Datum	
			8 5/8 " 325/200SX; 5 1/2 " 3425/150SX
			DST (1) 3197-3229 (LKC F&G) / 30-45-60-60, REC 725' MW, W / SCUM OIL, SIP 837-804#, FP 79-159 / 193-318#
ANH		769 + 1106	DST (2) 3259-3315 (LKC H,I,J) / 15-45-60-60, 2050' GIP, REC 50' OIL & GCM, 120' MGO, SIP 905-623#, FP 45-45 / 58-79#
TARK		2497- 622	
HEEB		3028-1153	DST (3) 3350-78 (LKC, ARB) / 15-45-60-60, 360' GIP, REC 460' CL GSY OIL, 240' MDY GSY OIL, SIP 1084-1062#, FP 56-109 / 136-272#, BHT 112'
TOR		3044-1169	
BR LM		3117-1242	
LKC		3129-1254	MICT - CO, PF (ARB) 3368-70, W / 1 SPF, AC 250G (15% NE-HCL), SWB LD, GSO, POP, P 50 BOPD, NW (GR 38%), 6/9/83
BKC		3364-1489	
ARB		3367-1492	
RTD		3430-1555	

NOTE: CORRECTION 5/26/83 - ORIGINALLY FIRST REPORTED IN 2640'FNL&330'FWL, SE/4

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS