

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-06614-00-00
Spot: NESWSW Sec/Twnshp/Rge: 31-12S-15W
990 feet from S Section Line, 4290 feet from E Section Line
Lease Name: WIELAND UNIT Well #: 2-7
County: RUSSELL Total Vertical Depth: 3060 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 8223 WILLOW PLACE SOUTH
HOUSTON, TX 77070

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.188	2977	0	w/unknown sxs cmt
SURF	6.625	2704	0	w/unknown sxs cmt

\$ 99.45

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/15/2007 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JEFF TEARE Company: CITATION OIL AND GAS CORPOR Phone: (281) 517-7199

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/15/2007 2:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Washed well down to 1500' - could not get back down - had bad area at 600'.
Ran tubing to 1000' - stacked out - pumped 40 sxs 60/40 pozmix - 10% gel cement.
Pulled to 600' - pumped 180 sxs cement with 200# hulls.
Pulled to 300' - pumped 80 sxs cement with 300# hulls - cement circulated.
POOH. Tied onto casing - pumped 100 sxs cement.
Had circulation up backside for a quite a while but quit.
Max. P.S.I. 400#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3010	3270		

INVOICED
DATE 7-6-07
INV. NO. 2008060040

Remarks: LEASE ORIGINALLY KNOWN AS JACOBS #7. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

10

Signed Case Morris
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

JUN 28 2007

CONSERVATION DIVISION
WICHITA KS

JUN 19 2007

[Handwritten signature]


15-167064-00-00

THE TEXAS COMPANY #7 JACOBS 31-12-15W
NE SW SW
970 FSL
Contr. _____ RUSSELL 4290 FEL County
E 1838 Comm. 8-8-35 Comp. 9-29-35 IP 232 BOPD

Tops	Depth	Datum
ANHY	890	
FT R	1755	
LAN S	2973	1135
TD	3060	

Casing
5" 3010

A/1000 1500 7333



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS