

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05507-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 15-15S-13W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SELLENS Well #: 1
County: RUSSELL Total Vertical Depth: 3329 feet

Operator License No.: 7383
Op Name: BOLDING, GRADY CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3326	0	175 SX
SURF	8.625	160	0	225 SX

\$ 108.19

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/26/2007 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: BOLDING, GRADY CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 200# hulls.
Plug thru casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2007 9:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Tied onto casing with backside opened - pumped 75 sxs - circulated up backside.
Shut in backside - pumped 175 sxs thru casing.
Started at 500# - broke to 350#.
Added 150# hulls to last 50 sxs.
Shut in at 150# P.S.I.

Perfs:

Top	Bot	Thru	Comments
3323	3329		

INVOICED
DATE 7-9-07
INV. NO. 2008060047

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 05 2007

CONSERVATION DIVISION
WICHITA, KS

JUN 29 2007

KEYES DRILLING CO

#1 SELLENS

15-15-13W
SW SW NW

Contr.

RUSSELL

Corr

E 1881

Comm 7-31-16


Comp. 8-29-16

IP 1.16 BOPD

Tops	Depth	Datum
ANHY	836	
TOP	271.8	
OROAD	3009	
LANS	304.8	
ARR	3323	
TD	3332	

Casing
8" 160
5" 3326

PB 3329
A/500, Swb 7 BOPH/6 hr
1100' OIH/8 hr
A/1000



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS