

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-033-21078-00-00
 Spot: SESENE Sec/Twnshp/Rge: 9-34S-18W
2295 feet from N Section Line, 340 feet from E Section Line
 Lease Name: COLE Well #: 1
 County: COMANCHE Total Vertical Depth: 6100 feet

Operator License No.: 32899
 Op Name: COMANCHE OPERATING, LLC
 Address: PO BOX 700534
SAN ANTONIO, TX 78270

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5125		WITH 2 SX CMT \$ 198.25
COND	20	40		WITH 10 SX CMT
PROD	4.5	5542	4000	WITH 140 SX CMT
SURF	8.625	620		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/12/2007 9:45 AM
 Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
 Proposal Rcvd. from: M. GREGG RYAN Company: COMANCHE OPERATING Phone: (432) 559-1725

Proposed Plugging Method: CIBP @ 5125' WITH 2 SX CMT. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 650' WITH 50 SX CMT 10 SX GEL AHEAD. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 06/12/2007 10:35 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5125' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1000' WITH 300# HULLS - 10 SX GEL - 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5276	5294		
5141	5146		

INVOICED
 DATE 7-9-07
 INV. NO. 2008060057

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed Eric MacLaren

RECEIVED
 (TECHNICIAN) KANSAS CORPORATION COMMISSION

JUL 02 2007 Form CP 27

CONSERVATION DIVISION
 WICHITA, KS

PBT