

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24641-00-00  
Spot: NWSENW Sec/Twnshp/Rge: 4-17S-24W  
1650 feet from N Section Line, 1550 feet from W Section Line  
Lease Name: ALBERS Well #: 1  
County: NESS Total Vertical Depth: 4530 feet

Operator License No.: 9067  
Op Name: DAMAR RESOURCES, INC.  
Address: PO BOX 70 234 W. 11TH, STE A  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	250		

\$147.23

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/28/2007 5:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 1800' WITH 50 SX CMT. 2ND PLUG AT 1020' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE  
Date/Time Plugging Completed: 06/28/2007 7:00 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG AT 1800' WITH 50 SX CMT. 2ND PLUG AT 1020' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.


Perfs:

INVOICED  
DATE 7-9-07  
INV. NO. 200806005-2

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Steve Durrant

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

JUL 02 2007

CONSERVATION DIVISION  
WICHITA, KS

PT