

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-205-19403-00-00  
Spot: NENWSE Sec/Twnshp/Rge: 12-30S-15E  
2609 feet from S Section Line, 1739 feet from E Section Line  
Lease Name: O AND E THOMPSON Well #: OW3-12  
County: WILSON Total Vertical Depth: 975 feet

Operator License No.: 33074  
Op Name: DART CHEROKEE BASIN OPERATING  
Address: 600 DART RD PO BOX 177  
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	975		
SURF	7	23		

\$ 35.00

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/09/2007 8:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Revd. from: TONY WILLIAMS Company: DART CHEROKEE BASIN OPERATI Phone: (620) 779-1531

Proposed Plugging Method: Run two cement strings to TD and fill from bottom to top

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE  
Date/Time Plugging Completed: 03/09/2007 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was lowered down the 2" production pipe to 950 ft. A one inch cement string was lowered down the outside of the 2" production pipe to 250 ft. The well was filled from bottom to top thru these cement strings. A total of 104 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

RECEIVED  
KCC DISTRICT #3

JUN 18 2007 AMD

CHANUTE, KS

INVOICED

DATE 7-9-07

INV. NO. 2008060053

Remarks:

Plugged through: CSG

District: 03

Signed

*Alan Dunning*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

JUN 25 2007

CONSERVATION DIVISION  
WICHITA, KS

PPT